



# TABLE OF CONTENTS SECTION 15

PAGE
15.0 EFFECTS ASSESSMENT SUMMARY TABLES
LIST OF TABLES
Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance 15-1
Table 15-2: Noise and Vibration - Summary of Potential Effects, Mitigation, Residual Effects and  Significance
Table 15-3: Greenhouse Gases - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-4: Groundwater - Summary of Potential Effects, Mitigation, Residual Effects and Significance .15-8
Table 15-5: Birch Lake System - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-6: Springpole Lake, North Basin System - Summary of Potential Effects, Mitigation, Residual  Effects and Significance
Table 15-7: Springpole Lake, Southeast Arm System - Summary of Potential Effects, Mitigation, Residual  Effects and Significance
Table 15-8: Local Inland Waterbodies - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-9: Fish and Fish Habitat - Summary of Potential Effects, Mitigation, Residual Effects and  Significance
Table 15-10: Vegetation Communities and Wetlands - Summary of Potential Effects, Mitigation, Residual  Effects and Significance
Table 15-11: Wildlife and Wildlife Habitat - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-12: Boreal Caribou - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-13: Wolverine - Summary of Potential Effects, Mitigation, Residual Effects and Significance 15-34
Table 15-14: Bats - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-15: SAR Birds - Summary of Potential Effects, Mitigation, Residual Effects and Significance 15-43
Table 15-16: Commercial Land and Resource Use - Summary of Potential Effects, Mitigation, Residual  Effects and Significance
Table 15-17: Outdoor Recreation - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-18: Local and Regional Economy - Summary of Potential Effects, Mitigation, Residual Effects and Significance
Table 15-19: Local and Regional Infrastructure and Services - Summary of Potential Effects, Mitigation, Residual Effects and Significance





Table 15-20: Traditional Land and Resource Use - Summary of Potential Effects, Mitigation, Residual Company of Potential Compa	lauk
Effects and Significance	15-58
Table 15-21: Archaeology - Summary of Potential Effects, Mitigation, Residual Effects and	
Significance	15-63
Table 15-22: Built Heritage Resources and Cultural Heritage Landscapes - Summary of Potential	Effects,
Mitigation, Residual Effects and Significance	15-64
Table 15-23: Human and Ecological Health - Summary of Potential Effects, Mitigation, Residual I	Effects and
Significance	15-65
Table 15-24: Indigenous People - Summary of Potential Effects, Mitigation, Residual Effects and	
Significance	15-68





#### 15.0 EFFECTS ASSESSMENT SUMMARY TABLES

#### Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	Phase <sup>1</sup>		Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	ਹ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
(Section 6.11), Human and Ecological Health	ction 6			ole Lake North Basin System (Section 6.7), Springpole Lake Southeast Arm System	,			
Without mitigation, there may be a change in criteria air parameters during construction, operation and closure. This could occur due to	•	•	•	Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants if required.  Site roads will be maintained in good condition, with regular inspections and	The modelled cumulative concentrations for suspended particulate matter, PM <sub>10</sub> , PM <sub>2.5</sub> ,	Ecological and Social Context: Level I Magnitude: Level I	Not Significant	High
the operation of equipment.	•	•	•	timely maintenance completed to minimize the silt loading on the roads.	nitrogen dioxide and sulphur	Geographic Extent: Level I		
	•	•	•	Vehicle speeds will be limited.	dioxide are below the respective Ambient Air Quality Criteria at the	Duration: Level II Frequency: Level III		
	_	•	_	<ul> <li>The process plant emission sources will be enclosed where possible and designed to allow good atmospheric dispersion. To reduce emissions, dust control equipment and best practices will be used, where necessary, as described below:</li> <li>Conveyor transfer (drop) points will be controlled via enclosure or water spray;</li> <li>Crushed ore stockpile will be enclosed, and emissions controlled by a baghouse;</li> <li>A wet scrubber or equivalent will be used to control emissions in grinding (baghouse controlled);</li> <li>Truck unloading at the primary crusher will be enclosed and emissions controlled by a baghouse;</li> <li>Drill rigs will be equipped with a dust shroud on the drill and a wet suppression (spray) system will be used;</li> <li>Truck placement of mine rock onto the co-disposal facility will be controlled using water sprays and surface wetting;</li> <li>Travel surfaces will be maintained to minimize silt (fine material);</li> <li>Crushing of ore materials and reclaim at stockpiles will be controlled by baghouses;</li> <li>The vents from the lime silo will be controlled by a dust collector;</li> <li>Areas for ore mixing and handling will be controlled by dust collectors; and,</li> <li>A regular maintenance schedule will be followed to ensure baghouses and dust collectors are functioning properly.</li> </ul>	extent of the property boundary and all points of reception during all Project phases. With the implementation of mitigation there will be an increase in criteria air parameters compared to baseline conditions. The residual effect is confined to the local study area and will occur continuously during the operation phase of the Project but is reversible at closure.	Reversibility: Level I		
	•	•	•	Air emissions from the use of diesel fuel for the mobile heavy equipment will be controlled through strategic mine scheduling to minimize the total distance travelled by haul trucks and other equipment and through the use of low sulphur diesel fuel.				
	•	•	•	A preventive maintenance program will be employed that encompasses all pollution control equipment, diesel-fired engines (vehicle, equipment and standby power generation) and all processes with the potential for air quality effects.				
	_	_	•	Exposed dust sources will be revegetated, and progressive reclamation will be conducted wherever appropriate to better control dust emissions from the mineral waste stockpiles and co-disposal facility.				
	_	•	_	Potentially acid generating mine rock will be placed in the co-disposal facility with thickened tailings being deposited into the mine rock gaps and voids from				





# Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance

Potential Effect(s)	ase <sup>1</sup>	Ö	Proposed Mitigation Measures <sup>2</sup>	Description	Residual Adverse Effect(s)	Significance of	
				2000р	Characterization <sup>3</sup>	Residual Adverse Effect	Prediction Confidence
			the perimeter dam to minimize the exposure of tailings that could generate dust. Further, the mine rock level will be maintained above the tailings to minimize the exposed tailings surface area.				
	_	•	Following completion of potentially acid generating mine rock disposal within the north cell of the co-disposal facility, non-acid generating tailings will be deposited over the entire north cell surface to fully cover the potentially acid generating mine rock and limit oxygen ingress. To minimize the exposure of tailings to winds generating dust, a vegetation cover will be established.				
•	•	-	A dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.				
	•	-	A blasting plan will be implemented and include measures to minimize the length of time the blasting material is allowed to sit in a drill hole before blasting. The blast schedule will optimize air dispersion to minimize effects on air quality, including by avoiding blasting during unfavourable meteorological conditions as needed.				
Without mitigation, there may be a change in metals during construction, operation and	•	•	Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants if required.	The modelled cumulative concentrations for metals are	Ecological and Social Context: Level I	Not Significant	High
closure. This could occur due to the operation of equipment.		-	<ul> <li>Vehicle speeds will be limited.</li> <li>The process plant emission sources will be enclosed where possible and designed to allow good atmospheric dispersion. To reduce emissions, dust control equipment and best practices will be used, where necessary, as described below: <ul> <li>Conveyor transfer (drop) points will be controlled via enclosure or water spray;</li> <li>Crushed ore stockpile will be enclosed, and emissions controlled by a baghouse;</li> <li>A wet scrubber or equivalent will be used to control emissions in grinding (baghouse controlled);</li> <li>Truck unloading at the primary crusher will be enclosed and emissions controlled by a baghouse;</li> <li>Drill rigs will be equipped with a dust shroud on the drill and a wet suppression (spray) system will be used;</li> <li>Truck placement of mine rock onto the co-disposal facility will be controlled using water sprays and surface wetting;</li> <li>Travel surfaces will be maintained to minimize silt (fine material);</li> <li>Crushing of ore materials and reclaim at stockpiles will be controlled by baghouses;</li> <li>The vents from the lime silo will be controlled by a dust collector;</li> <li>Areas for ore mixing and handling will be controlled by dust collectors; and</li> <li>A regular maintenance schedule will be followed to ensure baghouses and dust collectors are functioning properly.</li> </ul> </li> <li>Air emissions from the use of diesel fuel for the mobile heavy equipment will be controlled through strategic mine scheduling to minimize the total distance travelled by haul trucks and other equipment and through the use of low</li> </ul>	below the respective Ambient Air Quality Criteria at the extent of the property boundary and all points of reception during construction and operation. With the implementation of mitigation, emissions will result in an increase in the concentration of metals compared to baseline conditions. The residual effect is confined to the local study area and will occur continuously during the operation phase of the Project but is reversible at closure.	Magnitude: Level I Geographic Extent: Level I Duration: Level II Frequency: Level III Reversibility: Level I		





Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	) <sup>1</sup>			Residual Adverse Effect(s)		1
Potential Effect(s)	Con	do	ច	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	•	A preventive maintenance program will be employed that encompasses all pollution control equipment, diesel-fired engines (vehicle, equipment and standby power generation) and all processes with the potential for air quality effects.				
	_	_	•	Exposed dust sources will be revegetated, and progressive reclamation will be conducted wherever appropriate to better control dust emissions from the mineral waste stockpiles and co-disposal facility.				
	_	•	_	PAG mine rock will be placed in the co-disposal facility with thickened tailings being deposited into the mine rock gaps and voids from the perimeter dam to minimize the exposure of tailings that could generate dust. Further, the mine rock level will be maintained above the tailings to minimize the exposed tailings surface area.				
	_	_	•	Following completion of potentially acid generating mine rock disposal within the north cell of the co-disposal facility, non-acid generating tailings will be deposited over the entire north cell surface to fully cover the potentially acid generating mine rock and limit oxygen ingress. To minimize the exposure of tailings to winds generating dust, a vegetation cover will be established.				
	•	•	_	A dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.				
	•	•	-	A blasting plan will be implemented and include measures to minimize the length of time the blasting material is allowed to sit in a drill hole before blasting. The blast schedule will optimize air dispersion to minimize effects on air quality, including by avoiding blasting during unfavourable meteorological conditions as needed.				
Without mitigation, there may be a change in polycyclic aromatic compounds during construction, operation and closure. This could occur due to the operation of equipment.	-	•	_	Air emissions from the use of diesel fuel for the mobile heavy equipment will be controlled through strategic mine scheduling to minimize the total distance travelled by haul trucks and other equipment and through the use of low sulphur diesel fuel.	Under the expected construction and operating scenarios, the increase in the modelled concentrations of b(a)p due to the	Ecological and Social Context: Level I Magnitude: Level I Geographic Extent: Level I	Not Significant	High
	•	•	•	A preventive maintenance program will be employed that encompasses all pollution control equipment, diesel-fired engines (vehicle, equipment and standby power generation) and all processes with the potential for air quality effects.	Project will not exceed AAQC at the extent of the leased property boundary and all points of reception during all Project phases; however, the modelled cumulative concentration will exceed Ambient Air Quality Criteria due to the elevated baseline condition for benzo(a)pyrene.  With the implementation of mitigation measures, there will be an increase in the modelled concentrations of polycyclic aromatic compounds as represented by benzo(a)pyrene compared to baseline conditions. The residual effect is confined to the local study area and will occur	Duration: Level II Frequency: Level III Reversibility: Level I		





Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	) <sup>1</sup>			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ਹ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
					continuously during the operation phase of the Project but is reversible at closure.			
Without mitigation, there may be a change in other parameters during construction, operation and closure. This could occur due to the	•	•	•	Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray as needed, supplemented by dust suppressants if required.	The modelled cumulative concentrations of respirable silica, diesel particulate matter, and	Ecological and Social Context: Level I Magnitude: Level I	Not Significant	High
operation of equipment.	•	•	•	Vehicle speeds will be limited.	volatile organic compounds will	Geographic Extent: Level I		
	_	•	_	<ul> <li>The process plant emission sources will be enclosed where possible and designed to allow good atmospheric dispersion. To reduce emissions, dust control equipment and best practices will be used, where necessary, as described below: <ul> <li>Conveyor transfer (drop) points will be controlled via enclosure or water spray;</li> <li>Crushed ore stockpile will be enclosed, and emissions controlled by a baghouse;</li> <li>A wet scrubber or equivalent will be used to control emissions in grinding (baghouse controlled);</li> <li>Truck unloading at the primary crusher will be enclosed and emissions controlled by a baghouse;</li> <li>Drill rigs will be equipped with a dust shroud on the drill and a wet suppression (spray) system will be used;</li> <li>Truck placement of mine rock onto the co-disposal facility will be controlled using water sprays and surface wetting;</li> <li>Travel surfaces will be maintained to minimize silt (fine material);</li> <li>Crushing of ore materials and reclaim at stockpiles will be controlled by baghouses;</li> <li>The vents from the lime silo will be controlled by a dust collector;</li> <li>Areas for ore mixing and handling will be controlled by dust collectors; and</li> <li>A regular maintenance schedule will be followed to ensure baghouses and dust collectors are functioning properly.</li> </ul> </li> </ul>	not exceed the Ambient Air Quality Criteria at the extent of the leased property boundary and all points of reception during all phases. With the implementation of mitigation, emissions will result in an increase in the concentration of respirable silica, diesel particulate matter, and volatile organic compounds compared to baseline conditions The residual effect will be confined to the local study and will occur continuously during construction and operation phases of the Project but is reversible at closure.	Duration: Level II Frequency: Level III Reversibility: Level I		
	_	•	-	Air emissions from the use of diesel fuel for the mobile heavy equipment will be controlled through strategic mine scheduling to minimize the total distance travelled by haul trucks and other equipment and through the use of low sulphur diesel fuel.				
	_	•	_	Hydrogen cyanide emissions will be eliminated through the sulphur dioxide / oxygen cyanide treatment process to reduce cyanide in the tailings at the process plant and before deposition of tailings in the co-disposal facility. Excess sulphur dioxide used in this process will be recirculated (i.e., a closed-loop) without release to the air.				
-	•	•	•	A preventive maintenance program will be employed that encompasses all pollution control equipment, diesel-fired engines (vehicle, equipment and standby power generation) and all processes with the potential for air quality effects.				
	_	•	_	PAG mine rock will be placed in the co-disposal facility with thickened tailings being deposited into the mine rock gaps and voids from the perimeter dam to minimize the exposure of tailings that could generate dust. Further, the mine rock level will be maintained above the tailings to minimize the exposed tailings surface area.				
	-	_	•	Following completion of potentially acid generating mine rock disposal within the north cell of the co-disposal facility, non-acid generating tailings will be				





#### Table 15-1: Air Quality - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phas	e <sup>1</sup>	Residual Adverse Effect(s)				
Potential Effect(s)	Con	g	5	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				deposited over the entire north cell surface to fully cover the potentially acid generating mine rock and limit oxygen ingress. To minimize the exposure of tailings to winds generating dust, a vegetation cover will be established.				
	•	•	-	A dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.				
	•	•	_	A blasting plan will be implemented and include measures to minimize the length of time the blasting material is allowed to sit in a drill hole before blasting. The blast schedule will optimize air dispersion to minimize effects on air quality, including by avoiding blasting during unfavourable meteorological conditions as needed.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





#### Table 15-2: Noise and Vibration - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	Phase	,1		Residual Adverse Effect(s)				
Potential Effect(s)	Con	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	

#### **Noise and Vibration Valued Component (Section 6.3)**

- Area of Federal Jurisdiction: Fish and Fish Habitat, Migratory Birds, Species at Risk and Indigenous people
- Linkage from other VCs: None
- Linkage to other VCs: Fish and Fish Habitat (Section 6.10); Wildlife and Wildlife Habitat (Section 6.12); Woodland Caribou (Section 6.13); Wolverine (Section 6.15); SAR Birds (Section 6.16); Commercial Land and Resource Use (Section 6.17); Outdoor Recreation (Section 6.18): Traditional Land and Resource Use (Section 6.21)

Recreation (Section 6.18); Traditional Land and Re	esourc	e Use	(Section	on 6.21)				
Without mitigation, there may be a change in sound				Site equipment will be operated to meet NPC-300 and Health Canada	The noise prediction modelling	<b>Ecological and Social Context:</b>	Not Significant	High
levels during construction, operation and closure.	_	•		operational noise and vibration limits at points of reception, when applicable.	indicates that no exceedances of	Level I		
This could occur due to the operation of equipment.				Local Indigenous communities and identified points of reception will be advised	applicable limits are expected due to	Magnitude: Level II		
	•	_	_	ahead of transmission line construction work periods and as the construction work	activities at the mine site at the	Geographic Extent: Level I		
				proceeds.	identified points of reception and,	Duration: Level I		
				Work with local Indigenous communities to coordinate construction activities	therefore, no residual noise effects	Frequency: Level II		
	•	_	_	related to the transmission line to minimize overlap with the timing of traditional	from mine site activities are	Reversibility: Level I		
				land use activities (e.g., fall moose hunt) and other sensitive periods.	predicted	-		
				A mechanism will be established for receiving and responding to noise complaints	With the implementation of			
	•	•	•	in a timely manner during construction, operation and closure phases.	mitigation measures, there will be a			
	•	_	_	Construction of the transmission line will occur primarily during the daytime hours.	potential exceedance of noise criteria			
				Motorized equipment will be selected or designed with mufflers / silencers to limit	within 500 metres of the			
	•	•	•	noise emissions.	transmission line during			
				Reversing alarms should be dimmable with white noise and/or strobe lights, but	construction. The residual effect will			
	•	•	•	they will be in accordance with the applicable health and safety regulations.	be confined to the local study and			
				Regular inspections will take place to confirm that equipment and machinery used	occur intermittently during the			
	•	•	•	on site is operated in good working condition through regular maintenance.	period when construction will take			
				The use of engine brakes will be prohibited and engines will need to be stopped for	place near a confirmed point of			
	•	•	•	vehicles on standby, depending on seasons and weather.	reception that is in use and will be			
		1		Vehicles and equipment will be operated in such a way that impulsive noise is	fully reversible once construction in			
	•	•	•	minimized, where possible.	the area is complete.			
		<u> </u>		For helicopter use during transmission line construction, minimum flight altitudes				
	•	_	_	will be maintained unless the helicopters are engaged in construction tasks, landing				
				or departure.				
				Acoustical enclosures will be used in the process plant to limit overall noise				
	•	•	•	emissions from key noise sources, such as the ball mills.				
Without mitigation, there may be a change in				Site equipment will be operated to meet NPC-119, DFO and Health Canada	With the implementation of	Not applicable	Not applicable	High
vibration levels during construction, operation and	•	•	-	operational vibration limits at points of reception, when applicable.	mitigation measures, there is no	140t applicable	140t applicable	l light
closure. This could occur due to the operation of		<del>                                     </del>		Prior to construction, a detailed blasting plan will be developed for the Project	residual effect due to changes in			
equipment.				to determine the maximum allowable explosive loading at various locations	vibration levels during any phase of			
equipment.	•	•	-	within the Project Development Area to aid in complying with NPC-119,	the Project.			
				Health Canada and DFO limits for vibration at receptors.	and i roject.			
	•	•	-	A mechanism will be established for receiving and responding to vibration				
		1		complaints in a timely manner during construction, operation and closure phases.				

- 1 Con = Construction phase; Op = Operations phase; and, CI = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





#### Table 15-3: Greenhouse Gases - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	כ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<b>Greenhouse Gases Valued Component (Section 6.4</b>	.)							
Area of Federal Jurisdiction: Transboundary								
Linkage from other VCs: Air Quality (Section 6.2)								
Linkage to other VCs: Air Quality (Section 6.2)			1		Taget at the control of		N . C' . C'	1.2.1
Without mitigation, there may be a change in carbon dioxide, methane and nitrous oxide during construction, operation and closure. This could occur due to the operation of equipment.	•	•	•	<ul> <li>Implement the mitigation measures for air quality (Section 6.2.4), during the construction, operations and closures phases of the Project, including:         <ul> <li>During construction, operations and active closure, site roads will be maintained in good condition, with regular inspections and timely maintenance completed; and</li> <li>During operations, GHGs from the use of diesel fuel for the mobile heavy equipment will be minimized through strategic mine scheduling to minimize the total distance travelled by haul trucks and other equipment.</li> </ul> </li> </ul>	With the implementation of mitigation, there will be a minor increase in the emission of greenhouse gases of less than 0.1% of Canada's target during construction and operation phases, which will be continuous but reversible at closure. The emissions will contribute to	Ecological and Social Context: Level   Magnitude: Level   Geographic Extent: Level     Duration: Level    Frequency: Level     Reversibility: Level	Not Significant	High
	-	•	-	Construct a 230 kV transmission line to supply power during the operation of the Project, which obtains electricity from the Ontario grid.	atmospheric greenhouse gas concentrations beyond the regional			
	•	•	•	<ul> <li>A Greenhouse Gas Management Plan will be developed that will describe the energy and heat conservation, efficiency and management programs for the Project, and outline mitigation measures for GHG emissions during construction, operations and closure phases, including but not limited to the following: <ul> <li>Fuel use tracking on a regular basis (such as monthly);</li> <li>Limiting vehicle speeds;</li> <li>No-idling policies, where practicable and safe, to avoid unnecessary releases of greenhouse gas emissions;</li> <li>Regular maintenance and servicing of mining equipment and vehicles to maximize operational efficiency;</li> <li>Operational planning to minimize the distances haulage trucks travel on site to the extent possible; and</li> <li>Blast optimization to reduce the rehandling of materials.</li> </ul> </li></ul>				
	•	•	•	Implementation of Net-Zero Strategy to reduce the net greenhouse emissions over the life of the Project.				

#### Notes:

1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

2 Bolded text indicates a key mitigation measure.

3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-4: Groundwater - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	Phase <sup>1</sup>				Residual Adverse Effect(s)				
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
<ul> <li>Groundwater Valued Component (Section 6.5)</li> <li>Area of Federal Jurisdiction: Fish and Fish Habitat,</li> <li>Linkage from other VCs: none</li> <li>Linkage to other VCs: Surface Water (Sections 6.6)</li> </ul>		•		pecies at Risk and Indigenous people  Vegetation Communities and Wetlands (Section 6.11), and Traditional Land and Reso	ource Use (Section 6.21).				
Without mitigation, there may be a change in groundwater quantity during construction,	•	•	-	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of contact water that requires management.	The predicted change in groundwater discharge represents a negligible	<b>Ecological and Social Context:</b> Level I	Not Significant	High	
operation and closure. This could occur due to the dewatering of the open pit, and ongoing water	•	_	-	Strategic placement of the open pit dikes which limit and isolate the open pit basin and maintain 94% of Springpole Lake untouched by the Project.	component of the overall lake water balance for Birch and Springpole Lakes	Magnitude: Level   Geographic Extent: Level			
management throughout operations.	•	•	•	An integrated water management system will be operated to collect and control contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not used in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements.	or lake water levels. With the implementation of mitigation measures, there will be a residual effect due to a minor change in groundwater	Duration: Level II Frequency: Level I Reversibility: Level I			
	_	•	•	A geosynthetic clay liner will be installed on the upstream side of the perimeter embankment of the co-disposal facility south cell (specifically the south, west, and east sides) to mitigate seepage potential during the operation and closure phases.	flow of less than 0.2%. The residual effect will be confined to the Project Development Area within the local study				
	•	_	•	Revegetation and encouragement of natural revegetation / recolonization of disturbed areas, will be undertaken as part of progressive and final reclamation to minimize the length of time disturbed areas are exposed to reduce infiltration.	area, and will occur only throughout operation, but groundwater flow is expected to return to near baseline				
	_	-	•	During the filling of the open pit basin, accelerate the return of groundwater levels to baseline conditions, by transferring water from Springpole Lake in a controlled manner while maintaining lake water levels in Springpole Lake within natural variation.	conditions in the post-closure phase after cessation of open pit operations, and the filling of the open pit basin.				
Without mitigation, there may be a change in groundwater quality during construction, operation	•	•	_	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of contact water that requires management.	The change in groundwater quality due to seepage will not result in an	Ecological and Social Context: Level I	Not Significant	High	
and closure. This could occur due to the management of seepage from the co-disposal facility and ore stockpiles.	•	•	•	Locating the co-disposal facility on favourable geologic conditions at the Project site to support long-term stability and effective seepage management.	exceedance of surface water guidelines in the receiving water and there is unlikely to be an adverse effect to a	Magnitude: Level   Geographic Extent: Level   Duration: Level			
active and one stockpiles.	•	•	•	An integrated water management system will be operated to collect and control all contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not used in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements.	surface water system.  With the implementation of mitigation measures, there will be minor change in groundwater quality within the Project Development Area that will occur	Frequency: Level III Reversibility: Level II			
	•	•	_	Water collection ditches will be constructed and operated around the perimeter of key infrastructure, including the co-disposal facility and stockpiles, to collect overland flow and seepage and direct it to the integrated water management system.	frequently during the operation and closure phases that will be partially reversible with mitigation.				
	•	•	_	Best management practices (such as following approved blasting plans, and using appropriate drilling, explosive handling and loading procedures) will be implemented for the use of explosives to reduce the potential presence of					





#### Table 15-4: Groundwater - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				blasting residuals on mine rock stored in the co-disposal facility that could otherwise infiltrate into groundwater.				
	•	_	_	A geosynthetic clay liner will be installed on the upstream side of the perimeter embankment of the co-disposal facility south cell (specifically the south, west, and east sides) to mitigate seepage potential during the operation and closure phases.				
	•	-	•	Revegetation and encouragement of natural revegetation / recolonization of disturbed areas, will be undertaken as part of progressive and final reclamation to minimize the length of time disturbed areas are exposed to reduce infiltration.				

- 1 Con = Construction phase; Op = Operations phase; and, CI = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-5: Birch Lake System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>Surface Water: Birch Lake System Valued Compon</li> <li>Area of Federal Jurisdiction: Fish and Fish Habitat</li> <li>Linkage from other VCs: Air Quality (Section 6.2)</li> <li>Linkage to other VCs: Fish and Fish Habitat (Section 6.21), Human and Ecologic</li> </ul>	and Gr on 6.10	oundv 0), Veg	water ( getatio	on Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.1	1), Species at Risk (SAR) (Sections 6.13 to (	6.16), Outdoor Recreation (Section (	5.18), Traditional Lan	d and
Without mitigation, there may be a change in water quality during construction, operation and closure.  This could occur due to the changes in the catchment areas from site preparation and the construction and operation of mine site infrastructure such as the co-disposal facility.	•	•	-	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management.	The estimated changes to inflows to Birch Lake will not measurably affect water levels or velocities as the Birch	Ecological and Social Context: Level   Magnitude: Level	Not Significant	High
	•	•	-	<b>To reduce freshwater demand from Birch Lake, water recycling measures will be implemented.</b> For example, water collected in the co-disposal facility internal pond will be reclaimed and redirected to the plant / mill, minimizing the need for additional freshwater intake from the lake.	Lake system is outlet controlled. With the implementation of mitigation measures, there will be a minor decrease of 0.4% in the catchment	Geographic Extent: Level   Duration: Level   Frequency: Level    Reversibility: Level		
	•	•	•	Water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system. Noncontact water will be diverted away from Project components using ditches, diversion berms and other suitable measures.	area of Birch Lake that will affect base flows compared to baseline conditions. The residual effect will be confined within the Project Development Area and occur seasonally during construction and operation but will be fully reversible at closure.			
Without mitigation, there may be a change in water quality during construction, operation and closure.	•	•	-	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management.	The minor changes in some water quality parameters in Birch Lake will	Ecological and Social Context: Level I	Not Significant	High
This could occur due to site preparation activities, the operation of the co-disposal facility and other mine site infrastructure and final closure activities.	•	•	•	Maintain a minimum 120 m setback from Birch Lake to the co-disposal facility, the low-grade ore stockpile and the associated seepage collection system.	not exceed Water Quality Guidelines for the Protection of Aquatic Life. With the implementation of mitigation	Magnitude: Level   Geographic Extent: Level    Duration: Level		
·	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on air quality relevant to dust (Section 6.2.4), including:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed; and</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and</li> <li>Vehicle speeds will be limited.</li> </ul> </li> <li>Implementation of mitigation measures for potential effects on groundwater relevant to surface water (Section 6.5) including:         <ul> <li>Locating the co-disposal facility on favourable geologic conditions at the Project site to support long-term stability and effective seepage management; and</li> </ul> </li> </ul>	measures, there will be a minor change of water quality parameters compared to baseline conditions. The residual effect is conservatively predicted at assessment node 08 and will continue into post-closure for some parameters on a seasonal basis. The residual effect will be partially reversible, as most parameters return to baseline conditions.	Frequency: Level I Reversibility: Level II		





#### Table 15-5: Birch Lake System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	dO	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				During construction, a geosynthetic clay liner will be installed on the				
				upstream side of the perimeter embankment of the CDF south cell				
				(specifically the south, west and east sides) to mitigate seepage				
				potential during the operation and closure phases.				
				An integrated water management system will be designed to collect and control				
				contact water from the stockpiles, co-disposal facility and plant site areas.				
	•	•	•	Collected contact water that is not used in ore processing will be treated at the				
				effluent treatment plant and discharged to the southeast arm of Springpole Lake				
				in accordance with permitting requirements				
				An erosion and sediment control plan will be implemented to manage runoff				
				water around disturbed areas. The erosion and sediment control plan will be				
				prepared prior to the construction phase with the intent to minimize site erosion				
	•	•	•	and protect surface water from sedimentation. The erosion and sediment control				
				plan will provide further details on measures to minimize slope length and grade,				
				ditching and diversion berms, contact water management ponds, use of natural				
				vegetation buffers and runoff controls.				
				Water collection ditches will be constructed and operated around the				
				perimeter of infrastructure, including the co-disposal facility and stockpiles				
	•	•	•	to collect overland flow and seepage and direct it to the integrated water				
				management system. Non-contact water will be diverted away from Project				
				components using ditches, diversion berms and other suitable measures.				
				Best management practices (such as following approved blasting plans, and using				
	•	•	_	appropriate drilling, explosive handling and loading procedures) will be				
				implemented for the use of explosives used to reduce the potential presence of				
				blasting residuals in the open pit and on stockpiled mine rock and ore.				
				During construction and operation, co-manage and store potentially acid				
				generating mine rock and thickened non-acid generating tailings in the north cell				
	•	•	_	of the co-disposal facility. potentially acid generating mine rock will be				
				encapsulated with thickened non-acid generating tailings to isolate it from				
				atmospheric oxygen and mitigate potential acid generation and metal leaching.				
				In-plant destruction of cyanide in tailings using the sulphur dioxide / oxygen				
	-	•	-	treatment process to minimize residual cyanide and metals concentrations in the -				
				disposal facility.				
				Revegetation and encouragement of natural revegetation / recolonization of				
	-	•	•	disturbed areas will be undertaken as part of progressive and final reclamation to				
				minimize the length of time disturbed areas are exposed, to reduce erosion.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-6: Springpole Lake, North Basin System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>Surface Water: Springpole Lake, North Basin Syster</li> <li>Area of Federal Jurisdiction: Fish and Fish Habitat</li> <li>Linkage from other VCs: Air Quality (Section 6.2) a</li> </ul>	m (Second Gron 6.10	oundw	5.7) vater (S	Section 6.5) In Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11 6.24). Implementation of relevant mitigation measures for potential effects on surface water, as described in Section 6.6.4, including:  Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management;  During construction, operation and active closure, an integrated water management system will be designed to collect and control all contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with final permitting requirements, including the MDMER; and,  During construction, operation and active closure phases, water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system. Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures.  Strategic placement of the open pit dikes limits and isolates the open pit basin so that the Project directly affects only 6% of Springpole Lake surface area, while maintaining dam stability.  During controlled dewatering of the open pit basin, clean water will be		Characterization <sup>3</sup>	Residual Adverse Effect	Confidence
	•	_	-	pumped over the dikes at a rate consistent with the natural variability of Springpole Lake while water not suitable for direct discharge will be pumped to the central water storage pond to manage suspended sediments prior to discharge.  To reduce the overall volume of water required to refill the open pit basin and				
	_	•	-	support future fish habitat creation, recontouring of a portion of the north end of the open pit basin will be undertaken during operations.				
	_	-	•	Passive filling with precipitation and groundwater will be supplemented by water transferred from Springpole Lake in a controlled manner to reduce the fill time while maintaining lake water levels in Springpole Lake within the same order of magnitude and scale as existing conditions.				
	_	_	•	During filling of the open pit basin, efforts will also be made to minimize water takings during natural periods of low flow, to maintain lake levels within the same order of magnitude and scale as existing conditions of Springpole Lake.				





# Table 15-6: Springpole Lake, North Basin System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Without mitigation, there may be a change in water quality during construction, operation and closure. This could occur due to site preparation activities, controlled dewatering of the open pit basin, the operation of the CDF, and refilling of the open pit basin.	•	•	•	<ul> <li>Implementation of relevant mitigation measures for potential effects on air quality particularly for dust (Section 6.2.4) including:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> </ul> </li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul>	The minor changes in some water quality parameters in Birch Lake will not exceed Water Quality Guidelines for the Protection of Aquatic Life. With the implementation of mitigation measures, there will be a minor change of water quality parameters compared to baseline conditions. The residual effect is confined to the PDA and will continue into post-closure on a frequent basis. The residual effect will be partially reversible, as most parameters return to baseline conditions.	Ecological and Social Context: Level   Magnitude: Level   Geographic Extent: Level   Duration: Level     Frequency: Level     Reversibility: Level	Not Significant	High
	•	_	_	<ul> <li>Implementation of mitigation measures for potential effects on groundwater relevant to surface water (Section 6.5.4) including:         <ul> <li>Locating the co-disposal facility on favourable geologic conditions at the Project site to support long term stability and effective seepage management; and,</li> <li>During construction, a geosynthetic clay liner will be installed on the upstream side of the perimeter embankment of the co-disposal facility south cell (specifically the south, west, and east sides) to mitigate seepage potential during the operation and closure phases.</li> </ul> </li> </ul>				
	•	•	•	<ul> <li>Implementation of relevant mitigation measures for potential effects on surface water, as described in Section 6.6.4, including:         <ul> <li>Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management.</li> <li>During construction, operation and active closure, an integrated water management system will be designed to collect and control all contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with final permitting requirements, including the MDMER;</li> <li>During construction, operation and active closure phases, water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system. Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures;</li> <li>During construction, operation and active closure, an erosion and sediment control plan will be implemented to manage runoff water around disturbed areas. The erosion and sediment control plan will be prepared prior to the</li> </ul> </li> </ul>				





#### Table 15-6: Springpole Lake, North Basin System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				construction phase with the purpose of minimizing site erosion and protecting surface water from sedimentation. The erosion and sediment control plan will provide further details on measures to minimize slope length and grade, ditching and diversion berms, contact water management ponds, use of natural vegetation buffers and runoff controls;  • During construction and operation, best management practices (such as following approved blasting plans, and using appropriate drilling, explosive handling and loading procedures) will be implemented for the use of explosives use to reduce the potential presence of blasting residuals in the open pit and on stockpiled mine rock and ore;  • During construction and operation, co-manage and store potentially acid generating mine rock and thickened non-acid generating tailings in the north cell of the co-disposal facility. Potentially acid generating mine rock will be encapsulated with thickened non-acid generating tailings to isolate it from atmospheric oxygen and mitigate potential acid generation and metal leaching;  • During operations, in-plant destruction of cyanide in tailings using the SO2/O2 treatment process to minimize residual cyanide in the co-disposal facility; and,  • During operation and closure phases, revegetation and encouragement of natural revegetation / recolonization of disturbed areas will be undertaken as part of progressive and final reclamation to minimize the length of time disturbed areas are exposed, to reduce erosion.				
	•	_	_	During the construction of the dikes, turbidity curtains will be implemented to minimize sedimentation in Springpole Lake, as a proven measure used for in-water works.				
	•	-	_	During controlled dewatering of the open pit basin, clean water will be pumped over the dikes at a rate consistent with the natural variability of Springpole Lake while water not suitable for direct discharge will be pumped to the central water storage pond to manage suspended sediments prior to discharge.				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-7: Springpole Lake, Southeast Arm System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1						
Potential Effect(s)	Con	do	ם	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
Use (Section 6.21), Human and Ecological Health Without mitigation, there may be a change in water	and Gr on 6.10	oundv 0), Veg	vater (S	Section 6.5) n Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11), S Implement mitigation measures for potential effects on surface water (Section 6.6 and	During construction and operation	5.16), Outdoor Recreation (Section 6  Ecological and Social Context:	.18), Traditional Lanc	I and Resource High	
quantity during construction, operation and closure. This could occur due the controlled dewatering of the open pit basin, the discharge of treated effluent during operations and active closure and the refilling of the open pit basin during active closure.	•	•	•	<ul> <li>6.7.4), relevant to the southeast arm including:</li> <li>A compact mine site will be developed to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management;</li> <li>During controlled dewatering of the open pit basin, clean water will be pumped over the dikes at a rate consistent with the natural variability of Springpole Lake while water not suitable for direct discharge will be pumped to the central water storage pond to manage suspended sediments prior to discharge;</li> <li>To reduce the overall volume of water required to refill the open pit basin and support fish habitat development area creation, recontouring of a portion of the north end of the open pit basin will be undertaken during operations;</li> <li>Passive filling with precipitation and groundwater will be supplemented by water transferred from Springpole Lake in a controlled manner to reduce the fill time while maintaining lake water levels in Springpole Lake within the same magnitude and scale as existing conditions natural variation; and,</li> <li>During filling of the open pit basin, efforts will also be made to minimize water takings during natural periods of low flow, to maintain lake levels within the same magnitude and scale as existing conditions of Springpole Lake.</li> </ul>	phases, lake levels and flows in the southeast arm of Springpole Lake will be negligible and not expected to be measurably different than baseline conditions.  With the implementation of mitigation measures, the residual effect on the flows for the southeast arm of Springpole Lake will be a decrease up to 10% during active closure compared to baseline conditions. The residual effect will occur within the local study area with a certain degree of regularity during the active closure phase but will be fully reversible, when the open pit basin is refilled.	Level I  Magnitude: Level I  Geographic Extent: Level I  Duration: Level II  Frequency: Level II			
	_	•	•	Treated effluent will be discharged at a location where sufficient flow exists to reduce the potential for erosion at the discharge location.					
Without mitigation, there may be a change in water quality during construction, operation and closure. This could occur due to site preparation activities, and the discharge of treated effluent.	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on air quality relevant to dust (Section 6.2.4) including the following:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required; and,</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads.</li> <li>Vehicle speeds will be limited.</li> </ul> </li> <li>Implementation of mitigation measures for potential effects on groundwater relevant to surface water (Section 6.5.4) including:</li> </ul>	All modelled water quality parameters are predicted to remain below Water Quality Guidelines for the Protection of Aquatic Life within the southeast arm of Springpole Lake for all phases. With the implementation of mitigation measures, there will be a minor change in some water quality parameters compared to baseline conditions. The residual effect is confined to the local study	Ecological and Social Context: Level   Magnitude: Level   Geographic Extent: Level   Duration: Level    Frequency: Level	Not Significant	High	
	•	_	_	to surface water (Section 6.5.4) including:  • The co-disposal facility will be located on favourable geologic conditions at the Project site to support long-term stability and effective seepage management; and,	area and will occur continuously in operation and active closure but				





#### Table 15-7: Springpole Lake, Southeast Arm System - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	I	Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				<ul> <li>During construction, a geosynthetic clay liner will be installed on the upstream side of the perimeter embankment of the co-disposal facility south cell (specifically the south, west, and east sides) to mitigate seepage potential during the operation and closure phases.</li> </ul>	will be fully reversible at closure when discharge ceases.			
	•	•	•	<ul> <li>Implement mitigation measures for potential effects on surface water (Section 6.6.4 and 6.7.4), relevant to the southeast arm including the following:</li> <li>A compact mine site will be developed to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management;</li> <li>During construction, operations and active closure, an erosion and sediment control plan will be implemented to manage runoff water around disturbed areas. The erosion and sediment control plan will be prepared prior to the construction phase and provide further details on measures to minimize slope length and grade, ditching and diversion berms, contact water management ponds, use of natural vegetation buffers runoff controls, and working in and around water such as with the installation of the effluent discharge; and,</li> <li>During controlled dewatering of the open pit basin, clean water will be pumped over the dikes at a rate consistent with the natural variability of Springpole Lake while water not suitable for direct discharge will be pumped to the central water storage pond to manage suspended sediments prior to discharge.</li> </ul>				
	-	•	•	Treated effluent will be discharged at a location where sufficient flow exists to reduce the potential for erosion and promote assimilation at the discharge location. A diffuser or other means could be used to encourage greater mixing and attenuation of the effluent plume at the discharge location, if required. Consistent with MECP (2016) Policy B-1-5, the mixing zone size will be minimized to the extent practicable.				
	-	•	•	The effluent treatment plant will be designed and operated to produce an effluent quality appropriate for discharge to the environment in accordance with applicable regulatory requirements, including the MDMER. Best available technologies that are economical achievable will be considered for the effluent treatment plant to meet protection requirements. The effluent treatment plant will be refined with ongoing Project planning and engineering design, and as discharge criteria are finalized during the approvals process.				
Notes	•	•	-	<b>Domestic sewage will be treated to meet regulatory requirements before discharge to the environment.</b> Note that sewage treatment plant discharges will be combined with effluent treatment plant effluent before discharge to the southeast arm; and excess water in the central water storage pond will be treated at the effluent treatment plant, before being discharged to the southeast arm to maintain the site water balance.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-8: Local Inland Waterbodies - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	Phase	1		Description  Characterization <sup>3</sup> Residual Adverse Effect  Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section 6.18), Traditional Land and With the implementation of mitigation measures, there is no residual effect due to changes in water quantity for local inland waterbodies during any phase of the			
Con	do	ט	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Residual	Prediction Confidence
- nd Gr n 6.10	oundw )), Veg	ater (S etation	Section 6.5)	Species at Risk (SAR) (Sections 6.13 to (	5.16), Outdoor Recreation (Section	6.18), Traditional Lanc	I and Resource
•	•	_	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management.	With the implementation of mitigation measures, there is no	Not applicable	Not applicable	High
•	-	-	Watercourse crossings will be designed and constructed using best management practices such as appropriately sized structures (e.g., embedded culverts) to maintain hydraulic capacity and connectivity.	residual effect due to changes in water quantity for local inland waterbodies during any phase of the			
-	•	_	Inspect culverts periodically and remove accumulated material and debris upstream and downstream of the culverts to prevent erosion, flooding, and mobilization of sediment.	Project.			
•	_	_	Construction of the transmission line during frozen conditions to minimize effects on waterbodies and watercourses within the PDA of the transmission line corridor.				
•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on air quality relevant to dust (Section 6.2.4) including:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul> </li> </ul>	With the implementation of mitigation measures, there is no residual effect due to changes in water quality for local inland waterbodies during any phase of the Project.	Not applicable	Not applicable	High
•	-	-	<ul> <li>Implementation of mitigation measures for potential effects on groundwater relevant to surface water (Section 6.5.4) including:         <ul> <li>Locating the co-disposal facility on favourable geologic conditions at the Project site to support long term stability and effective seepage management; and,</li> <li>During construction, a geosynthetic clay liner will be installed on the upstream side of the perimeter embankment of the co-disposal facility south cell (specifically the south, west, and east sides) to mitigate seepage potential during the operation and closure phases.</li> </ul> </li> </ul>				
•	-	_	Development of a compact mine site to limit the areal extent of disturbance, and to limit the overall areas of site contact water that requires management.  An erosion and sediment control plan will be prepared an implemented prior to the construction phase with the intent to minimize site erosion and protect surface water from sedimentation. The erosion and sediment control plan will provide further details on measures to minimize erosion, sedimentation and				
	mmpond Gran 6.10 Section	mponent (some of the section of the	mponent (Section of Groundwater (Section 6.10), Vegetation Section 6.24).	mponent (Section 6.9)  Indicated Section 6.9)  Indicated Section 6.9  Indicated Section 6.9	Proposed Mitigation Measures2   Description	Proposed Mitigation Measures2  Description  Characterization1  mponent (Section 6.5) n6.10), Vegetation Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11), Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section 6.24).    Vegetation Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11), Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section 6.24).    Vegetation Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11), Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section 6.24).    Vegetation Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11), Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section 6.24).    Vegetation Communities and Wetlands (Section 6.11), Wildlife and Wildlife Habitat (Section 6.11). Species at Risk (SAR) (Sections 6.13 to 6.16), Outdoor Recreation (Section Section 2.49.    With the implementation of mitigation measures for posterial special and devise upstream and downstream of the culters to prevent erosion, flooding, and mobilization of sediment.    Vegetation of the transmission line during frozen conditions to minimize effects on waterbodies and watercourses within the PDA of the transmission line corridor.    Vegetation of the transmission line during frozen conditions to minimize effects on waterbodies and watercourses within the PDA of the transmission line corridor.    Vegetation of the transmission line during frozen conditions to minimize effects on a department plan will be implementation of mitigation measures, there is no residual effect due to changes in water Ociocal minimate to dust (Section 6.24) including:    Vegetation of water spray and supplemented by dust suppressants; if required;    Vegetation of water spray and supplemental stockplies will be controlled through water during any phase of the Project.    Vegetation of water spray and supplemental stockplies will	Proposed Mitigation Measures  Description  Description  Description  Characterization  Significance of Residual Adverse Effect  Adverse Effect  Description  Description  Characterization  Significance of Residual Adverse Effect  Adverse Effect  Description  Description  Characterization  Significance of Residual Adverse Effect  Adverse Effect  Description (S.24).  Development of a compact mine site to limit the areal extent of disturbance, and to imit the overall areas of site contact where that requires management, and adverse that requires tructures (e.g., embedded curvers) to maintain hydraulic capacity and connectivity.  Description  Watercourse crossings will be designed and constructed using best management; plan and downstream of the culverts to prevent erosion, flooding, and mobilization of sciedment.  Description  Description  Description  Description  Characterization  Significance of Residual Adverse Effect  Adverse Effect  Adverse Effect  With the implementation of mission measures for the intervity of the changes in water quantity for lock changes in water quantity for lock thanges in water quantity for local inland waterbodies during any phase of the Project.  During construction, operations and active closure, a dust management plan will be implemented.  During construction, operations and active closure, a dust management plan will be implementation of mitigation measures for potential effects on variety evaluation of water spray and supplemented by dust suppressants, if required:  Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required:  Site roads will be maintained in good condition, with regular inspections and timely maintained in good condition, with regular inspections and timely maintained in good condition, with regular inspections and timely maintained in good condition, with regular inspections and timely maintained in good condition, with regular inspections and timely maintained in





#### Table 15-8: Local Inland Waterbodies - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	ob	CI	Proposed Mitigation Measures <sup>2</sup>	Description	Significance of Residual Adverse Effect	Prediction Confidence	
	•	•	_	During construction and operation, best management practices (such as following approved blasting plans, and using appropriate drilling, explosive handling and loading procedures) will be implemented for the use of explosives use to reduce the potential presence of blasting residuals in the open pit and on stockpiled mine rock and ore.				
	_	•	_	Inspect culverts periodically and remove accumulated material and debris upstream and downstream of the culverts to prevent erosion, flooding, and mobilization of sediment.				
	•	_	_	Construction of the transmission line during frozen conditions to minimize effects on waterbodies and watercourses within the Project Development Area of the transmission line corridor.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase	1		Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	Cl	Proposed Mitigation Measures <sup>2</sup>	Description Charact	terization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>Fish and Fish Habitat Valued Component (Section of Area of Federal Jurisdiction: Fish and Fish Habitat</li> <li>Linkage from other VCs: Noise and Vibration (Section of Linkage to other VCs: Commercial Land and Resonant Component (Section of Page 1)</li> </ul>	tion 6			ce Water Systems (Section 6.6 to 6.9) .17), Outdoor Recreation (Section 6.18), Traditional Land and Resource Use (Section 6.	21), Human and Ecological Health (Section 6.24)			
Without mitigation, there may be a change in fish habitat during construction, operation and closure.  This is due to ground disturbance during site preparation activities that may lead to	•	•	•	Minimize the mine site footprint and overprinting of waterbodies where possible.  During construction (and other phases as applicable), implement a site-specific erosion and sediment control plan to mitigate the entry of sediment into surrounding waterbodies.	With the implementation of mitigation measures, there is no residual effect due to changes in fish habitat during any phase of the Project.  Not applicable	•	Not applicable	High
sedimentation in fish habitat, changes in catchment areas that may change water flows in fish habitat, the construction of the co-disposal facility, dikes, central water storage pond and other mine site infrastructure that will overprint fish habitat, and construction of fish habitat offsetting measures.	•	_	_	Install isolation measures for in-water works associated with the construction of the dikes in the north basin of Springpole Lake and water crossings following the guidance of DFO's Interim Standard: In-Water Site Isolation (DFO 2023a).	any phase of the Project.			
	•	•	•	Complete required maintenance of in-water structures following the guidance of DFO's Interim Code of Practice: Repair and Maintenance of In-Water Structures (DFO 2023b).				
	•	•	•	<ul> <li>Implement the measures outlined in the Fish Habitat Offsetting and Compensation Plan (Appendix F), including:</li> <li>Overbuild and integrate spawning shoals along the active lake-facing embankments of the dikes to replace Lake Trout and Lake Whitefish spawning opportunities lost within the dewatered basin;</li> <li>Coordinate with the provincial government (Ministry of Mines) to implement the reclamation of fish habitat at the abandoned South Bay Mine;</li> <li>Implement the investigation and study of Lake Sturgeon in the Birch River and Cat River system and consider measures to reinstate or augment the population;</li> <li>Place coarse wood structure along Springpole Lake shorelines currently lacking structural diversity;</li> <li>Construct a new and significant embayment (46 ha fish habitat development area) to the east of the dewatered area to be functional at closure;</li> <li>Enhance the open pit basin (dewatered) area for selected key species (determined during engagement and consultation) by modifying cover, structure and substrates to improve habitat suitability where appropriate;</li> <li>Contour the north end of the main open pit and the Phase 1 pit and optimize fish habitat structures, substrates and depth for selected key species as determined during engagement and consultation; and,</li> <li>Restore flow to unnamed lake L-1 on completion of mining and filling of the dewatered basin.</li> </ul>				
Without mitigation, there may be a change to fish communities during construction, operation and closure.	•	_	_	Install isolation measures for in-water works associated with the construction of the dikes in the north basin of Springpole Lake and water crossings following the guidance of DFO's Interim Standard: In-Water Site Isolation (DFO 2023a).	With the implementation of mitigation measures, there is no residual effect due to changes in fish communities during any phase of the Project.	2	Not applicable	High





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
This is due to the construction of the dikes and other mine site infrastructure, the controlled	•	•	•	Relocate fish from the work area prior to undertaking in-water works for the construction of Project infrastructure.				
dewatering of the open pit basin, the operation of the water intake structure, and the use of explosives during construction and operation.	•	_	-	Prior to dewatering the open pit basin area, conduct a comprehensive fish removal program (fish-out) within the basin to minimize the unintentional death of fish.				
		•	•	Undertake in-water construction activities outside of the fish spawning and egg incubation periods to reduce the potential for effect on fish as per DFO's Measures to Protect Fish and Fish Habitat (DFO 2023c) and the MNR's inwater timing windows (MNR 2013), unless exempt.				
	•	•	•	Prohibit fishing and hunting within the controlled access portion of the Project Development Area by Project personnel while working or residing on site.				
	•	•	•	Prior to construction, develop a detailed blasting management plan for areas adjacent to fish habitat that meets DFO criteria or alternate values derived in consultation with DFO.				
	•	•	•	Install screens or use other measures at water intakes to prevent entrainment or impingement of fish as per the DFO Code of Practice (DFO 2020).				
Without mitigation, there may be a change in fish health during construction, operation and closure.  This is due to ground disturbance during site	•	•	•	During construction (and other phases as applicable), implement a site-specific erosion and sediment control plan to mitigate the entry of sediment into surrounding waterbodies.	With the implementation of mitigation measures, there is no residual effect due to changes in fish health during	Not applicable	Not applicable	High
preparation activities that may lead to sedimentation in fish habitat, the construction of the	•	•	-	Design culverts to provide fish passage and naturalized substrates to mitigate habitat impacts.	any phase of the Project.			
dikes and other mine site infrastructure, the controlled dewatering of the open pit basin, the operation of the co-disposal facility and ore stockpiles, and the discharge of the treated effluent.	•	•	•	Implement the measures to mitigate effects on surface water, as outlined in Section 6.6.4, Section 6.7.4 and Section 6.8.4, including the <b>treatment of mine</b> effluent prior to discharging to the southeast arm of Springpole Lake, and the collection and management of runoff and seepage water from the perimeter of the co-disposal facility and ore stockpiles.				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	atory E Groun	Birds; lı ıdwate	ndige r (Sec		on 6.17), Outdoor Recreation (Section 6.18	3), Traditional Land and Resource Us	se (Section 6.21), Hur	man and
Without mitigation, there may be a change in the	•	_	_	Development of a compact mine site to limit the areal extent of disturbance.	Vegetation communities are common	<b>Ecological and Social Context:</b>	Not Significant	High
relative abundance and diversity of plant species and vegetation communities during construction,	•	-	_	Co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.	throughout the LSA and RSA, and therefore, removal in the PDA is	Level I  Magnitude: Level I		
operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine	•	•	_	Minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and safe operation.	unlikely to threaten the long-term viability of vegetation communities. With the implementation of mitigation	Geographic Extent: Level   Duration: Level    Frequency: Level		
access road and the transmission line, ongoing maintenance of the infrastructure, and the activities associated with final reclamation at closure.	•	•	_	Minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs.	measures, the residual effect is a loss of less than 1% within the regional study area of vegetation communities compared to baseline conditions. The	Reversibility: Level II		
	•	•	_	<ul> <li>Undertake progressive rehabilitation of mine development areas, in accordance with a filed Closure Plan under the Mining Act. The progressive rehabilitation measures for the Project may include:</li> <li>Removal of construction-related facilities and reclamation of disturbed lands, if not required during operations;</li> <li>Rehabilitation of aggregate sources when no longer required for the Project;</li> <li>Implementation of a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and avoids the use of non-native or invasive species; and</li> <li>Preserving organic material in place where reasonable and/or stockpiling material onsite.</li> </ul>	residual effect is confined to the Project Development Area and will occur once during construction but will be partially reversible as portions of the Project Development Area (i.e. co-disposal facility embankments) will not be fully revegetated at post-closure.			
	-	-	•	During the active closure phase of the Project, undertake final rehabilitation activities of the mine development areas to create a stable, productive, and naturalized state. The plan includes the rehabilitation of disturbed lands (using commercially available native seed sources) and the establishment of self-sustaining vegetative cover.				
	-	-	•	Vehicular access will be restricted along the mine access road, and the road will be scarified to alleviate surface compaction to aid in vegetative regeneration during the closure phase.				
Without mitigation, there may be a change in the		_		Development of a compact mine site to limit the areal extent of disturbance.	There will be a minimal change in the	<b>Ecological and Social Context:</b>	Not Significant	High
function, connectivity, and quality during construction, operation and closure.	•	_	_	Co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.	abundance of vegetation communities and significant wildlife habitat within	Level I  Magnitude: Level I		
This is due to the mine access road and the transmission line, the operation of the processing facility, open pit, haul roads and mine access road	•	•	•	Mechanical vegetation removal practices will be used, when possible.  Implement mitigation measures for potential effects on air quality relevant to	the regional study area due to the	Geographic Extent: Level I  Duration: Level III  Frequency: Level II		

vegetation communities and wetlands (Section 6.2.4) including:

During construction, operations and active closure, a dust management

plan will be implemented to identify potential sources of fugitive dusts,

existing routes for linear corridors.

With the implementation of mitigation

measures, the residual effect will be a

Frequency: Level II

Reversibility: Level II

facility, open pit, haul roads and mine access road

wetlands due to dust.

which may lead to indirect effects on vegetation and





		Phase <sup>1</sup>	ı		F	esidual Adverse Effect(s)		
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				outline mitigation measures that will be employed to control dust	decrease of terrestrial communities			
				generation and detail the inspection and record keeping required to	(0.36%) and wetland communities			
				demonstrate that fugitive dusts are being effectively managed;	(0.14%) compared to baseline			
				Dust emissions from roads and mineral stockpiles will be controlled through	conditions. The residual effect will be			
				the application of water spray and supplemented by dust suppressants, if	confined to the local study area and			
				required;	occur intermittently through all phases			
				Site roads will be maintained in good condition, with regular inspections and	of the Project and will be partially			
				timely maintenance completed to minimize the silt loading on the roads;	reversible as portions of the Project			
				and,	Development Area (i.e. co-disposal			
				Vehicle speeds will be limited.	facility embankments) will not be fully			
				Implement mitigation measures for potential effects on groundwater relevant to	revegetated at post-closure.			
				vegetation communities (Section 6.5.4), including the following:				
				During operation and closure phases, revegetation and encouragement of      The property of the property				
				natural revegetation / recolonization of disturbed areas, will be undertaken as part of progressive and final reclamation to minimize the length of time				
	•	•	-	1 ' ' 3				
				<ul> <li>disturbed areas are exposed to reduce infiltration; and,</li> <li>During the filling of the open pit basin, accelerate the return of groundwater</li> </ul>				
				levels to baseline conditions, by transferring water from Springpole Lake in a				
				controlled manner while maintaining lake water levels in Springpole Lake				
				within natural variation.				
				Minimize the clearing of vegetation within the mine access road and				
	•	•	-	transmission line corridor as feasible.				
				Minimize the removal of woody vegetation within the transmission line corridor to				
				maintain natural cover to adjacent areas. The removal of woody vegetation will be				
	•	•	_	limited to hazard trees and clearing to provide safe construction access and				
				infrastructure needs.				
				An invasive species management plan will be implemented during				
				construction, operation and active closure phases to reduce the spread of				
				invasive and non-native species from the Project, and include the following				
				measures:				
				Construction equipment arriving on the Project site will be clean and free of				
				any plant or soil material;				
				Where necessary, establish designated cleaning areas onsite to prevent or				
	•			limit the spread of invasive and non-native species;				
	•		•	Where necessary, store stripped topsoil from the construction of the transmission line corridor in designated locations to avoid the introduction of				
				invasive and non-native species from the existing disturbances due to				
				forestry activities;				
				<ul> <li>If required, topsoil stripped in or near areas with identified invasive and non-</li> </ul>				
				native species will be managed and stored in designated locations, where				
				practical; and,				
				To limit the introduction of invasive and non-native species, certificates of				
				seed analysis will be requested for seed mixes where available.				
				1 Jees analysis will be requested for seed mixes where available.				1





		Phase	,1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	CI	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	_	<ul> <li>Undertake progressive rehabilitation of mine development areas, in accordance with a filed Closure Plan under the <i>Mining Act</i>. The progressive rehabilitation measures for the Project may include:</li> <li>Removal of construction-related facilities and reclamation of disturbed lands, if not required during operations;</li> <li>Rehabilitation of aggregate sources when no longer required for the Project;</li> <li>Implementation of a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and avoids the use of non-native or invasive species; and</li> <li>Preserving organic material in place where reasonable and/or stockpiling material onsite.</li> </ul>				
	_	-	•	During the active closure phase of the Project, undertake final rehabilitation activities of the mine development areas to create a stable, productive, and naturalized state. The plan includes the rehabilitation of disturbed lands (using commercially available native seed sources) and the establishment of self-sustaining vegetative cover.				
	_	_	•	Vehicular access will be restricted along the mine access road, and the road will be scarified to alleviate surface compaction to aid in vegetative regeneration during the closure phase.				
Without mitigation, there may be a change in	•	_	_	Development of a compact mine site to limit the footprint of disturbance.	As wetlands are common throughout	Ecological and Social Context:	Not Significant	High
relative abundance and area of wetland extent	•	_	-	Co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.	the local and regional study area, the removal within the Project	Level I  Magnitude: Level I		
during construction, operation and closure. This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line, ongoing maintenance of the infrastructure, the operation of the processing facility, open pit, haul roads and mine access road which may lead to indirect effects, and the activities associated with final reclamation at closure.	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on air quality relevant to vegetation communities and wetlands (Section 6.2.4) including:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul> </li> </ul>	Development Area is not expected to threaten the long-term viability of wetland communities.  With the implementation of mitigation measures, the residual effect will be a decrease of less than 0.19% of wetlands compared to baseline conditions. The residual effect is confined to the Project Development Area, and will occur once during construction, but will continue through all phases and will be partially reversible as it will not be fully revegetated at post-closure.	Geographic Extent: Level I Duration: Level III Frequency: Level I Reversibility: Level II		
	•	•	•	<ul> <li>Implement mitigation measures for potential effects on groundwater relevant to wetlands (Section 6.5.4), including the following:</li> <li>During operation and closure phases, revegetation and encouragement of natural revegetation / recolonization of disturbed areas, will be undertaken as part of progressive and final reclamation to minimize the length of time disturbed areas are exposed to reduce infiltration; and,</li> </ul>				





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	Cl	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				During the filling of the open pit basin, accelerate the return of groundwater levels to baseline conditions, by transferring water from Springpole Lake in a controlled manner while maintaining lake water levels in Springpole Lake within natural variation.				
	•	•	•	<ul> <li>During construction, operation and active closure phases, implement the following mitigation measures for wetlands:         <ul> <li>Conduct construction activities in wetlands during late summer, fall or winter, whenever practical;</li> <li>Salvage topsoil and the upper organic layer when constructing in and adjacent to wetlands;</li> <li>Isolate work areas prior to construction using feasible techniques when working in wetlands during the open water period;</li> <li>Install silt fences prior to construction on approaches to wetlands to prevent erosion and sedimentation, and remove silt fencing once the disturbed areas are stabilized.</li> </ul> </li> </ul>				
	•	•	1	<ul> <li>During construction and operation phases, undertake progressive rehabilitation of mine development areas, in accordance with a filed Closure Plan under the Mining Act. The progressive rehabilitation measures for the Project may include:         <ul> <li>Removal of construction-related facilities and reclamation of disturbed lands, if not required during operations;</li> <li>Rehabilitation of aggregate sources when no longer required for the Project;</li> <li>Implementation of a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and avoids the use of non-native or invasive species; and</li> <li>Preserving organic material in place where reasonable and/or stockpiling material onsite.</li> </ul> </li> </ul>				
	-	-	•	During the active closure phase of the Project, undertake final rehabilitation activities of the mine development areas to create a stable, productive, and naturalized state. The plan includes the rehabilitation of disturbed lands (using commercially available native seed sources) and the establishment of self-sustaining vegetative cover. The closure phase will also include consultation with communities on opportunities for wetland creation.				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		hase	e <sup>1</sup>		R	esidual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul><li>Linkage from other VCs: Noise and Vibration (Sec</li><li>Linkage to other VCs: Local and Regional Econom</li></ul>	atory I tion 6 ny (Sec	Birds 5.3), F	; Indig ish an	enous people; Change in the Environment that are Directly Linked or Incidental to A d Fish Habitat (Section 6.10), Vegetation Communities and Wetlands (Sections 6.11),	Wildlife and Wildlife Habitat (Section 6.12)			
Without mitigation, there may be a change in the relative abundance of wildlife habitat during construction, operation and closure.	•	-	_	Develop of a compact mine site to limit the areal extent of disturbance.  Co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.	Wildlife habitat is common throughout the regional study area and there is a low potential for the Project to adversely affect	Ecological and Social Context: Level   Magnitude: Level	Not significant	High
This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line, ongoing maintenance of the infrastructure, and the activities associated with final reclamation at closure.	•	•		Follow appropriate timing windows for vegetation removals; in combination with timing windows for Boreal Caribou (6.13), Wolverine (6.14), bats (Section 6.15), and SAR birds (6.16), vegetation removals should only occur between September 15 to January 14. Note that construction activity should never occur during the critical breeding period for Bald Eagle, defined as March 5 to August 31 in northwest Ontario.	wildlife habitat throughout the local and regional study area. With the implementation of mitigation measures, the residual effect is the loss of 1.21% of the habitat for Fisher in the regional study area, and less than 5% of the	Geographic Extent: Level I Duration: Level III Frequency: Level I Reversibility: Level II Timing: I		
	•	•	-	Permits for specially protected species under the Fish and Wildlife  Conservation Act may be required to remove dens, nests, and lodges.  Undertake progressive revegetation in the mine site area, where	habitat for Osprey. The residual effect is confined to the Project Development Area, occurs once during construction, and will			
	•	_	_	practicable, during operation of the Project.  During construction, minimize the disturbance by using existing trails and roads for travel, where practicable.	avoid sensitive periods of wildlife use. The residual will continue until post-closure but is partially reversible as site conditions			
	•	•	•	<ul> <li>Implement the mitigation measures for potential effects on vegetation communities and wetlands relevant to bat (Section 6.11.4) including:         <ul> <li>During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and safe operation;</li> <li>During construction and operation, minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs;</li> <li>During construction, operation and active closure phases, implement mitigation measures for wetlands;</li> <li>During operation and closure phases, undertake progressive and final rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and wildlife habitat features.</li> </ul> </li> </ul>	within the Project Development Area will be altered until post-closure although some areas of the Project Development Area will not be revegetated (i.e., the codisposal facility).			
Without mitigation, there may be a change in the function, connectivity, and quality of wildlife habitat during construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in sensory disturbances, ongoing maintenance of the		-	-	Co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible;  Maintain existing hydroperiod conditions, outside the zone of influence for dewatering, by directing water from dewatering activities away from terrestrial habitats, where possible;	Wildlife habitat is common throughout the regional study area and changes due the Project will have a low potential to adversely affect wildlife and/or the habitat required for wildlife to carry out the life	Ecological and Social Context: Level   Magnitude: Level    Geographic Extent: Level   Duration: Level	Not significant	High
	•	_	Follow appropriate timing windows for vegetation removals; in combination with timing windows for Boreal Caribou (6.13), Wolverine	processes necessary to survive and reproduce.	Frequency: Level II Reversibility: Level I			





	Р	hase	1		Re	sidual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
infrastructure resulting in sensory disturbances, and the activities associated with final reclamation at closure.				(6.14), bats (Section 6.15), and SAR birds (6.16), vegetation removals should only occur between September 15 to January 14. Note that construction activity should never occur during the critical breeding period for Bald Eagle, defined as March 5 to August 31 in northwest Ontario.	With the implementation of mitigation measure, the indirect changes on the function, connectivity and quality of wildlife			
	•	•	•	During construction, operation and closure, where practicable, avoid sensitive wildlife habitat by implementing buffers (Table 6.127) around sensitive habitats. The implementation of buffers will be sufficient to mitigate acoustic effects on birds (Rodgers and Schwikert 2002).	habitat will result in a residual effect of less than 1% loss of habitat for most wildlife species, a 1 to 2% loss of habitat for Fisher, beaver and Wood frog, and a 2 and 3% loss			
	-	•	•	Undertake progressive revegetation in the mine site area, where practicable, during operation of the Project.  During construction, minimize the disturbance by using existing trails and	of habitat for Red-eyed Vireo within the regional study area.  The residual effect is confined to the local			
	•	•	_	roads for travel, where practicable.	study area and occur intermittently during			
	•	_	_	<ul> <li>During construction of the mine access road and transmission line:</li> <li>Minimize the area cleared with heavy machinery for the construction of the mine access road, as practicable, recognizing the need for clear sightlines for safety; and</li> <li>Minimize the removal of woody vegetation along the transmission line by limiting removal to hazard trees and only clearing for safe access and infrastructure need.</li> </ul>	operations and may occur during sensitive wildlife periods. It is expected to be fully reversible at closure.			
	•	•	•	<ul> <li>Implement the mitigation measures for air quality relevant to wildlife (Section 6.2.4) including:</li> <li>During construction, operation and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed;</li> <li>Routine maintenance of all pollution control equipment, diesel-fired engines (vehicle, equipment and standby power generation);</li> <li>The process plant emission sources will be enclosed where possible and be designed to allow good atmospheric dispersion, and dust control equipment such as dust collectors and water sprays will be used together with best practices, where necessary, to reduce emissions;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul>				
	•	•	•	<ul> <li>Implement the mitigation measures for noise and vibration relevant to wildlife (Section 6.3.4) including:</li> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible;</li> </ul>				





	Р	hase	1		Re	esidual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				<ul> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills;</li> <li>Generator intakes and exhausts in the process plant will use silencers;</li> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions;</li> <li>Reversing alarms will be dimmable with white noise and/or strobe lights;</li> <li>The use of engine brakes will be prohibited;</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible;</li> <li>Regular inspections will take place to confirm that equipment and machinery used on site is operated in good working condition through regular maintenance; and,</li> <li>For helicopter use during transmission line construction, minimum flight altitudes will be maintained unless the helicopters are engaged in construction tasks, landing or departure.</li> </ul>				
	•	•	•	<ul> <li>During construction, operation and closure phases, implement mitigation measures for lighting to minimize sensory disturbance (Appendix J), including:         <ul> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms; and,</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practicable.</li> </ul> </li> </ul>				
	•	•	•	<ul> <li>Implement the mitigation measures surface water systems relevant to wildlife (Section 6.6.4) including:         <ul> <li>During construction, operation and active closure, an integrated water management system will be operated to collect and control contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not used in ore processing will be treated at the ETP and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements;</li> <li>During construction, operation and active closure, contact water collection ditches will be constructed and operated around the perimeter of key infrastructure, including the co-disposal facility and stockpiles, to collect overland flow and seepage and direct it to the integrated water management system;</li> <li>Locating the co-disposal facility on favourable geologic conditions at the Project site to support long-term stability and effective seepage management; and,</li> <li>Discouraging wildlife from inhabiting contact water ponds (including the co-disposal facility and central water storage ponds).</li> </ul> </li> </ul>				
	•	•	•	Implement the mitigation measures for potential effects on vegetation communities and wetlands relevant to wildlife (Section 6.11.4) including:				





	F	Phase <sup>1</sup>		R	esidual Adverse Effect(s)		
Potential Effect(s)	Con	do ;	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
			<ul> <li>During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and safe operation;</li> <li>During construction and operation, minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs; and,</li> <li>During operation and closure phases, undertake progressive and final rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and wildlife habitat features.</li> </ul>				
Without mitigation, there may be a change in the risk of mortality of wildlife during construction,	•	• -	Develop of a compact mine site to limit the areal extent of disturbance.  Co-locate the transmission line, airstrip and mine access road within a shared	With the implementation of mitigation measures, such as timing windows during construction, strictly enforcing speed limits	Ecological and Social Context: Level   Magnitude: Level	Not significant	High
operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in the loss of habitat and the use of equipment, ongoing operation of the mine access road, and the activities associated with final reclamation at	•	• -	infrastructure corridor, where feasible;  Follow appropriate timing windows for vegetation removals; in combination with timing windows for Boreal Caribou (6.13), Wolverine (6.14), bats (Section 6.15), and SAR birds (6.16), vegetation removals should only occur between September 15 to January 14. Note that construction activity should never occur during the critical breeding period for Bald Eagle, defined as March 5 to August 31 in northwest Ontario.	and properly managing domestic waste, there may a minor residual effect due to the change in the risk of mortality for some wildlife species, The residual effect will be confined to the Project Development Area, and may occur infrequently through	Geographic Extent: Level   Duration: Level   Frequency: Level   Reversibility: Level   Timing:		
closure.	•	•	During construction, operation and closure, where practicable, avoid sensitive wildlife habitat by implementing buffers (Table 6.127) around sensitive habitats. The implementation of buffers will be sufficient to mitigate acoustic effects on birds (Rodgers and Schwikert 2002).	construction, operation and active closure during sensitive wildlife periods, but is reversible at closure.			
	•	• -	Permits for specially protected species under the Fish and Wildlife  Conservation Act may be required to remove dens, nests, and lodges.				
	•	•	During construction, operation and closure, prohibit hunting and trapping within the gated controlled access portion of the Project Development Area by Project personnel while working or residing on-site, during construction, operation and closure phases				
	•	•	During construction, operation and closure phases, domestic solid waste products and similar materials will be properly secured, stored and disposed of at an offsite licensed facility, particularly anything that is an attractant for scavenging wildlife. Domestic solid waste products will be transported to a landfill off site, mitigating the habitat sink effect of increased predator densities that can be created due to access to landfill sites.				
	•	• -	<ul> <li>During the operation phase of the mine access road and transmission line:</li> <li>Enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings;</li> </ul>				





	P	has	e <sup>1</sup>		Re	esidual Adverse Effect(s)		
Potential Effect(s)	Con	dO	Ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				Project-related vehicles travelling on the mine access road must come				
				to a stop if wildlife is encountered and provide them with the right-of-				
				way to cross the road; and				
				Minimize vegetation management along the transmission line corridor to				
				that necessary for safe operation.				
				During construction, operation and closure, wildlife awareness training will				
	_			be provided to Project employees.				
				During construction, operation and closure, log (and report as needed)				
	•	•	•	observed wildlife, sign / tracks and wildlife-vehicle collisions and alter				
				mitigation measures as appropriate.				
				Implement measures outlined in a spill prevention and contingency plan to				
	•	•	•	be developed prior to construction.				

#### Notos

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-12: Boreal Caribou - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1		Description Characterization Residual Confid			
Potential Effect(s)	Con	do	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Residual	Prediction Confidence
Linkage to other VCs: Commercial Land and Resort				n (Section 6.3), Vegetation Communities and Wetlands (Section 6.11) 5.17), Traditional Land and Resource Use (Section 6.21), Human and Ecological Healt				
Without mitigation, there may be a direct change in Boreal Caribou habitat during construction,	•	•	•	Development of a compact mine site to limit the areal extent of disturbance.	With the implementation of mitigation measures, the residual effect due to	<b>Ecological and Social Context:</b> Level II	Not Significant	Moderate to Hight
operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line resulting in the direct loss of wolverine habitat and the indirect loss due to a change in sensory disturbance.	•	•	•	During construction, co-locate the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.	direct habitat changes is a 0.10% reduction in GHD Category 1	Magnitude: Level II Geographic Extent: Level I		
	•	•	•	Align the new transmission line route adjacent to the existing E1C transmission line corridor, to the extent possible, to reduce the creation of new linear corridors.	Calving/Nursery Habitat, a 0.03% reduction in GHD Category 1 wintering habitat, and a 0.26% reduction in GHD	Duration: Level III Frequency: Level I Reversibility: Level I		
	•	•	•	During construction of the Project, minimize the disturbance in Category 1 and 2 Boreal Caribou habitats by using existing trails and roads for travel.	Category 2 habitat available in the Churchill Range.	Timing:		
	•	•	•	<ul> <li>In collaboration with Indigenous communities and MECP, design and implement a habitat restoration program for Boreal Caribou, that includes:         <ul> <li>The creation of suitable Boreal Caribou calving habitat through the reclamation of a small island in the open pit basin of Springpole Lake and revegetate the island with mature coniferous forest;</li> <li>The development of suitable restoration of habitat of existing disturbed areas for Boreal Caribou; and,</li> <li>The deferral of forestry and mineral exploration lands where suitable Boreal Caribou habitat exists.</li> </ul> </li> </ul>	With the application of mitigation measures, including measures to avoid, minimize, restore and offset habitat losses, the residual effect is minor and <1% change at RSHA scale. The residual effect is confined to the local study area, however the effects may only be fully mitigated once the habitat returns after closure. The residual effect will occur			
	•	•	•	During construction, operation and closure phases, implement relevant mitigation measures for noise from Section 6.3.	once during construction phase, and predicted to be partially reversible			
		•	<ul> <li>During construction of the mine access road and transmission line:</li> <li>Minimize the area cleared with heavy machinery in Category 1 Boreal Caribou habitat to the extent possible recognizing the need for clear sightlines for safety along the mine access road;</li> <li>Reduce predator sight lines by minimizing the removal of woody vegetation along the transmission line in Boreal Caribou location clusters and adjacent to Category 1 habitat (overwintering and calving) by limiting removal to hazard trees and only clearing for safe access and infrastructure needs;</li> <li>Avoid clearing and construction activities in Category 1 Boreal Caribou nursery habitat during the calving and nursery period (May 1 to September 15); and</li> <li>During construction and operation of the airstrip, avoid construction and overflights of Category 1 nursery habitats during the nursery period (May 1 to September 15).</li> <li>Efforts will be made to re-supply the mine with bulk of deliveries aiming to be outside the calving period.</li> </ul>	during revegetation at closure and includes offsetting objectives that will be immediately implemented to offset habitat loss in the short term (Level I) as regrowth of the vegetation supporting Boreal Caribou will occur over time but site conditions within the PDA will be permanently altered and some areas of the PDA will not be revegetated (i.e., CDF) at post-closure. The timing of the residual effect is low as the construction activities will not occur during the sensitive nursery period for Boreal Caribou.				





Table 15-12: Boreal Caribou - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Without mitigation, there may be a direct change in Boreal Caribou habitat during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line resulting in the direct loss of wolverine habitat and the indirect loss due to a change in sensory disturbance.	•	•	•	<ul> <li>During construction, operation and closure phases of the Project, implement relevant mitigation measures for dust from Section 6.2, including:</li> <li>The process plant emission sources will be enclosed where possible and be designed to allow good atmospheric dispersion.</li> <li>During construction, operations and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul>	The predicted residual effect due the indirect loss of habitat from sensory disturbance includes a 0.49% reduction in GHD Category 1 Nursery Habitat, a 0.9% reduction in GHD Category 1 Winter Use Habitat, and a 0.83% reduction in GHD Category 2 habitat at the RSHA scale. Nursery habitat functions are maintained elsewhere in the RSHA.  With the application of mitigation measures, including measures to avoid, minimize, restore and offset residual habitat losses, the indirect habitat changes occur at RSHA scale but are minor and < 1% change.	Ecological and Social Context: Level    Magnitude: Level    Geographic Extent: Level   Duration: Level    Frequency: Level    Reversibility: Level   Timing:	Not Significant	Moderate to Hight
	•	•	•	<ul> <li>During construction, operation and closure phases, implement relevant mitigation measures for noise from Section 6.3, including:</li> <li>Motorized equipment will be selected or designed with mufflers/silencers to limit noise emissions;</li> <li>Reversing alarms should be dimmable with white noise and/or strobe light but in accordance with the applicable health and safety regulations;</li> <li>Check that equipment and machinery used on site is maintained in good working conditions through regular maintenance and inspection;</li> <li>Prohibit the use of engine brakes and require the engines to be stopped for vehicles on standby, depending on seasons and weather;</li> <li>Operate vehicles and equipment such that impulsive noise is minimized, where possible; and,</li> <li>For helicopter use during transmission line construction, maintain minimum flight altitudes unless engaged in construction tasks, landing or departure</li> </ul>	The residual effect is confined to the LSA and will be fully mitigated once the sensory disturbance is discontinued at closure. The residual effect will occur intermittently throughout construction and operations, however it will be reversible at closure when sensory disturbances will cease. The timing of the residual effect will not occur during the sensitive nursery period for Boreal Caribou			
	•	•	•	<ul> <li>During construction, operation and closure phases of the Project, implement mitigation for lighting to minimize sensory disturbance, including:         <ul> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms; and,</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practical.</li> </ul> </li> </ul>				
Without mitigation, there may be a change in range conditions for Boreal Caribou during construction, operation and closure.	•	•	•	During construction, operation and closure phases of the Project, implement the relevant mitigation measures for wildlife from Section 6.12.  Do not disturb encountered Boreal Caribou, during all phases of the Project.	With the application of mitigation measures, including measures to avoid, minimize, restore and offset residual	Ecological and Social Context: Level II Magnitude: Level II	Not Significant	Moderate to Hight
This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the	•	•	•	During the operation of the mine access road and transmission line:  Reduce Project-related traffic speed along the mine access road in sections traversing Category 1 habitat during seasonally sensitive	habitat losses, the residual effect occurs at RSHA scale but are minor and < 1% change. The residual effect of direct	Geographic Extent: Level I Duration: Level III Frequency: Level II		





# Table 15-12: Boreal Caribou - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
transmission line resulting in the direct loss of wolverine habitat and the indirect loss due to a change in sensory disturbance.				<ul> <li>periods, particularly along segments with identified crossing locations;</li> <li>Project-related vehicles travelling on the mine access road must come to a stop if Boreal Caribou are encountered and provide them with the right-of-way and time to safely cross the roadway and into native cover without undue sensory disturbance;</li> <li>Minimize vegetation management along the transmission line corridor within Category 1 habitat to that necessary for safe operation; and,</li> <li>In areas where Boreal Caribou have been recorded crossing the existing transmission line, retain vegetation and undertake strategic vegetation treatments to reduce the potential for barriers to movement.</li> <li>If Boreal Caribou are found to be crossing linear features created by the Project in new areas (outside of the currently identified cluster of movement locations), implement vegetation treatments to mitigate potential barrier effects in these new locations.</li> <li>A controlled access gatehouse/checkpoint and signage are proposed to control unauthorized use of the 18-km mine access road leading to the mine site. An access management strategy will be developed with local Indigenous communities and MNR to provide access for traditional land and resource use activity along this newly accessible area. Efforts will be made to re-supply the mine with bulk of deliveries aiming to be outside the calving period.</li> </ul>	habitat removal is confined to the LSA. The duration of the residual effect may only be fully mitigated once the habitat returns after closure. The residual effect will occur intermittently throughout construction and operations. The residual effect will be partially reversible as regrowth of the vegetation supporting Boreal Caribou will occur over time but site conditions within the PDA will be permanently altered and some areas of the PDA will not be revegetated (i.e., CDF) at post-closure and includes offsetting objectives that will be immediately implemented to offset habitat loss in the short term. The residual effect will not occur during the sensitive nursery period.	Reversibility: Level II Timing: II	Adverse Effect	
	•	•	•	<ul> <li>During the closure of the Project, incorporate Boreal Caribou habitat features into the overall closure plan, where possible, including:         <ul> <li>Revegetate suitable areas within the PDA using species that will support the development of mature coniferous refuge habitat for Boreal Caribou, and incorporate the restoration of lichen and lichen treatments in select areas; and,</li> <li>Remove or otherwise regraded stockpiles (including surficial soil and ore) to facilitate Boreal Caribou access.</li> </ul> </li> <li>In collaboration with Indigenous communities and MECP, design and implement a habitat restoration program for Boreal Caribou, that includes:         <ul> <li>The creation of suitable Boreal Caribou calving habitat through the</li> </ul> </li> </ul>				
	•	•	•	<ul> <li>reclamation of a small island in the open pit basin of Springpole Lake and revegetate the island with mature coniferous forest;</li> <li>The development of suitable restoration of habitat of existing disturbed areas for Boreal Caribou; and,</li> <li>The deferral of forestry and mineral exploration lands where suitable Boreal Caribou habitat exists.</li> <li>The application of mitigation measures to specific pathways and phases are illustrated in</li> </ul>				





#### Table 15-12: Boreal Caribou - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	Phase <sup>1</sup>			Residual Adverse Effect(s)				
Potential Effect(s)	Con		C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				Table 6.14-4. Mitigation measures described in this section are expected to be effective for their intended purposes given their effective implementation on similar Projects.				
	•	•	•	<ul> <li>To meet regulatory requirements, FMG is advancing various potential offsetting opportunities including:         <ul> <li>Opportunities to undertake enhanced restoration of lands subject to recent forest fires.</li> <li>Opportunities to undertake enhanced restoration on lands subject to forestry activities through partnership with the forestry industry.</li> <li>Opportunities identified by Ontario pursuant to the provincial Woodland Caribou Recovery Strategy. For example, potential habitat restoration in the vicinity of the abandoned South Bay mine.</li> <li>Partnership deferrals in other parts of the Churchill Range</li> <li>At closure, the Project includes the construction of a Boreal Caribou calving island (linked to the Project's fish habitat development area)</li> </ul> </li> </ul>				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, CI = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-13: Wolverine - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase <sup>1</sup>			Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	IJ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				n (Section 6.3), Vegetation Communities and Wetlands (Section 6.11)  i.17), Traditional Land and Resource Use (Section 6.21), Human and Ecological Health (S  Development of a compact mine site to limit the footprint of disturbance.  During all phases of the Project, limit the removal of moderate and high-quality Wolverine habitat within the PDA, as practicable.  Prior to the construction phase of the Project, undertake pre-construction winter aerial surveys to map activity centres and potentially active natal or maternity dens within a 10 km buffer of the PDA.  Implementation of mitigation measures for potential effects on air quality relevant to Wolverine (Section 6.1.4) including:  Control dust emissions from roads and mineral stockpiles through the application of water spray and supplemented by dust suppressants, if required.  Maintain site roads in good condition, with regular inspections and timely	Wolverine habitat is common throughout the local and regional study area, and there is a low potential to adversely affect Wolverine or their habitat to carry out the life processes necessary to survive and reproduce.  With the implementation of mitigation measures, the residual effect is the loss of 0.2% of the available habitat and the alteration of	Ecological and Social Context: Level   Magnitude: Level    Geographic Extent: Level   Timing: Level    Duration: Level     Frequency: Level     Reversibility: Level	Not significant	Moderate
	•	•	•	<ul> <li>maintenance completed to minimize the silt loading on the roads.</li> <li>Limit vehicle speeds.</li> <li>Implementation of mitigation measures for potential effects on noise relevant to Wolverine (Section 6.3.4) including:</li> <li>Select or design motorized equipment with mufflers / silencers to limit noise emissions.</li> <li>Use reversing alarms that are dimmable with white noise and/or strobe light but in accordance with the applicable health and safety regulations.</li> <li>Check that equipment and machinery used on site is maintained in good working conditions through regular maintenance and inspection.</li> <li>Prohibit the use of engine brakes and require the engines to be stopped for vehicles on standby, depending on seasons and weather.</li> <li>Operate vehicles and equipment such that impulsive noise is minimized, where possible.</li> <li>For helicopter use during transmission line construction, maintain minimum flight altitudes unless engaged in construction tasks, landing or departure.</li> <li>During construction, operations and closure phases of the Project, implement</li> </ul>	10% of the available habitat in the regional study area. The residual effect is confined to the local study area, occurs continuously during all phases, and may not avoid sensitive periods for Wolverine. The residual effect will continue until post-closure but is reversible when Project activities end.			
	•	•	•	<ul> <li>mitigation for lighting to minimize sensory disturbance, including the following:</li> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms.</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practicable.</li> </ul>				
	•	_	_	<ul> <li>During construction of the mine site area, the mine access road and the transmission line, implement the following mitigation:         <ul> <li>Avoid the removal of vegetation during the nursery period for Wolverine (January 1 to April 30), when in moderate and high-quality habitat.</li> <li>In the event of a Wolverine observation or encounter within the construction area, cease Project activities within the construction area</li> </ul> </li> </ul>				





	Phase <sup>1</sup>		1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				<ul> <li>and the surrounding 500 m until the individual is no longer present within 500 m of the construction area.</li> <li>In the event a den site is observed or encountered within the construction area, cease all Project activities within 8 km of the den site until a Qualified Professional has assessed the den site. If the den site is deemed active by the Qualified Professional, implement additional Wolverine protective measures as determined in consultation with relevant government agencies.</li> </ul>				
	•	1	_	<ul> <li>During construction of the mine access road and transmission line, implement the following mitigation:         <ul> <li>Minimize the area cleared with heavy machinery for the construction of the mine access road, as practicable, recognizing the need for clear sightlines for safety.</li> <li>Minimize the removal of woody vegetation along the transmission line by limiting removal to hazard trees and only clearing for safe access and infrastructure needs.</li> </ul> </li> </ul>				
	-	•	-	<ul> <li>During the operation of the mine access road, implement the following mitigation:         <ul> <li>Minimize vegetation management along the transmission corridor to that necessary for safe operation.</li> <li>Enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings.</li> <li>Project-related vehicles travelling on the mine access road must come to a stop if wildlife is encountered and provide them with the right-of-way to cross the road.</li> </ul> </li> </ul>				
	_	•	-	<ul> <li>During operation of the transmission line, implement the following mitigation:</li> <li>Minimize vegetation management along the transmission corridor to that necessary for safe operation.</li> <li>Maintain natural vegetation structure and composition to the extent possible for Wolverine habitat connectivity, in areas along the transmission line identified as moderate or high-quality habitat for Wolverine.</li> </ul>				
	_	-	•	<ul> <li>During the closure of the Project restore disturbed Wolverine habitat, implement the following mitigation:         <ul> <li>Remove any infrastructure and install physical barriers to prevent vehicular access.</li> </ul> </li> <li>Replant disturbed areas and monitor vegetation reestablishment; many of the offsetting measures targeted towards other species (e.g., Caribou) will benefit Wolverine and their habitats.</li> </ul>				





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ט	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Without mitigation, there may be a change in movement for wolverine during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line resulting in the direct loss of wolverine habitat and the indirect loss due to a change in sensory disturbance.	•	-	_	<ul> <li>Development of a compact mine site to limit the footprint of disturbance.</li> <li>Implementation of mitigation measures for potential effects on noise relevant to Wolverine (Section 6.3.4) including:         <ul> <li>Select or design motorized equipment with mufflers / silencers to limit noise emissions.</li> <li>Use reversing alarms that are dimmable with white noise and/or strobe light but in accordance with the applicable health and safety regulations.</li> </ul> </li> </ul>	The change in movement is a temporary change in behaviour, that is not expected to have long-term impacts on the population of wolverine.  With the implementation of mitigation measures, the residual	Ecological and Social Context: Level   Magnitude: Level    Geographic Extent: Level   Timing: Level    Duration: Level     Frequency: Level	Not significant	Moderate
	•	•	•	<ul> <li>Check that equipment and machinery used on site is maintained in good working conditions through regular maintenance and inspection.</li> <li>Prohibit the use of engine brakes and require the engines to be stopped for vehicles on standby, depending on seasons and weather.</li> <li>Operate vehicles and equipment such that impulsive noise is minimized, where possible.</li> <li>For helicopter use during transmission line construction, maintain minimum flight altitudes unless engaged in construction tasks, landing or departure.</li> </ul>	effect due to a change in movement is moderate. The residual effect is confined to the local study area, will occur continuously throughout all phases, and may occur during sensitive periods for wolverine. It is fully reversible at closure.	Reversibility: Level I		
	•	_	-	<ul> <li>During construction of the mine site area, the mine access road and the transmission line, implement the following mitigation:</li> <li>Avoid the removal of vegetation during the nursery period for Wolverine (January 1 to April 30), when in moderate and high-quality habitat.</li> <li>In the event of a Wolverine observation or encounter within the construction area, cease Project activities within the construction area and the surrounding 500 m until the individual is no longer present within 500 m of the construction area.</li> <li>In the event a den site is observed or encountered within the construction area, cease all Project activities within 8 km of the den site until a Qualified Professional has assessed the den site. If the den site is deemed active by the Qualified Professional, implement additional Wolverine protective measures as determined in consultation with relevant government agencies.</li> </ul>				
	•	-	_	<ul> <li>During construction of the mine access road and transmission line, implement the following mitigation:         <ul> <li>Minimize the area cleared with heavy machinery for the construction of the mine access road, as practicable, recognizing the need for clear sightlines for safety.</li> <li>Minimize the removal of woody vegetation along the transmission line by limiting removal to hazard trees and only clearing for safe access and infrastructure needs.</li> </ul> </li> </ul>				
	_	•	_	<ul> <li>During the operation of the mine access road, implement the following mitigation:</li> <li>Minimize vegetation management along the transmission corridor to that necessary for safe operation;</li> <li>Enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings; and,</li> </ul>				





		Phase	,1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				Project-related vehicles travelling on the mine access road must come to a stop if wildlife is encountered and provide them with the right-of-way to cross the road.				
		•	-	<ul> <li>During operation of the transmission line, implement the following mitigation:         <ul> <li>Minimize vegetation management along the transmission corridor to that necessary for safe operation; and,</li> <li>Maintain natural vegetation structure and composition to the extent possible for Wolverine habitat connectivity, in areas along the transmission line identified as moderate or high-quality habitat for Wolverine.</li> </ul> </li> </ul>				
	_	_	•	<ul> <li>During the closure of the Project restore disturbed Wolverine habitat, implement the following mitigation:         <ul> <li>Remove any infrastructure and install physical barriers to prevent vehicular access; and,</li> <li>Replant disturbed areas and monitor vegetation reestablishment; many of the offsetting measures targeted towards other species (e.g., Caribou) will benefit Wolverine and their habitats.</li> </ul> </li> </ul>				
Without mitigation, there may be a change in the risk of mortality of wolverine during construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in the loss of habitat and the use of equipment, ongoing operation of the mine access road, and the	•	•	•	Any person who engages in Project activities will be provided education and awareness training by a Qualified Professional, prior to entering the site to perform any Project activities. Training will address existence of Protected Species on site; identification of Protected Species and their habitats; awareness of Wolverine on roads within site to avoid collisions; the care that should be taken to avoid Protected Species individuals and/or their habitat; appropriate actions to take if any Protected Species is encountered; and how to record impacts to the Protected Species.	With the proposed design and mitigation measures, residual effects due to change in the risk of mortality is not predicted and therefore a determination of significance is not required.	Not applicable	Not applicable	Moderate
activities associated with final reclamation at closure.	•	_	_	Prior to the construction phase of the Project, undertake pre-construction winter aerial surveys to map activity centres and potentially active natal or maternity dens within a 10 km buffer of the Project Development Area.				
	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on wildlife and wildlife habitat relevant to Wolverine (Section 6.12.4) including:         <ul> <li>Provide any person who engages in Project activities with education and awareness training prior to entering the site to perform any Project activities. Training will address existence of Protected Species on site, identification of Protected Species and their habitats, awareness of Wolverine on roads within site to avoid collisions, the care that should be taken to avoid Protected Species individuals and/or their habitat, appropriate actions to take if any Protected Species is encountered; and how to record impacts to the Protected Species.</li> <li>Log (and report as needed) observed wildlife, sign / tracks and wildlife-vehicle collisions and alter mitigation measures as appropriate.</li> <li>Properly secure, store and dispose of all domestic solid waste products and similar materials at an offsite licensed facility, particularly anything</li> </ul> </li> </ul>				





		Phase <sup>1</sup>	I			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	Ū	Proposed Mitigation Measures <sup>2</sup>	Description Characterization <sup>3</sup>		Significance of Residual Adverse Effect	Prediction Confidence
				that is an attractant for scavenging wildlife. All domestic solid waste products will be transported to a landfill off site and therefore mitigating the habitat sink effect of increased predator densities that can be created due to access to landfill sites.  During construction of the mine site area, the mine access road and the				
	•	_	-	<ul> <li>transmission line, implement the following mitigation:</li> <li>Avoid the removal of vegetation during the nursery period for Wolverine (January 1 to April 30), when in moderate and high-quality habitat.</li> <li>In the event of a Wolverine observation or encounter within the construction area, cease Project activities within the construction area and the surrounding 500 m until the individual is no longer present within 500 m of the construction area.</li> <li>In the event a den site is observed or encountered within the construction area, cease all Project activities within 8 km of the den site until a Qualified Professional has assessed the den site. If the den site is deemed active by the Qualified Professional, implement additional Wolverine protective measures as determined in consultation with relevant government agencies.</li> </ul>				
	_	•	-	<ul> <li>During the operation of the mine access road, implement the following mitigation:         <ul> <li>Minimize vegetation management along the transmission corridor to that necessary for safe operation.</li> <li>Enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings.</li> <li>Project-related vehicles travelling on the mine access road must come to a stop if wildlife is encountered and provide them with the right-of-way to cross the road.</li> </ul> </li> </ul>				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





Phase <sup>1</sup> Residual Adverse Effect(s)								
Potential Effect(s)	Con	do	IJ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>Bats Valued Component (Section 6.15)</li> <li>Area of Federal Jurisdiction: Species at Risk</li> <li>Linkage from other VCs: Noise (Section 6.3), Veget</li> <li>Linkage to other VCs: Human and Ecological Healt</li> </ul>				es and Wetlands (Section 6.11)				
Without mitigation, there may be a change in the	•	_	_	Develop a compact mine site to limit the areal extent of disturbance.	Bat maternity and foraging habitats	Ecological and Social Context:	Not significant	Moderate
relative abundance of bat habitat during	•	-		Co-locate the transmission line, airstrip and mine access road within a shared	are common throughout the local and	Level I		
construction, operation and closure.				infrastructure corridor, where feasible.	regional study area, and there is a low	Magnitude: Level I		
This is due to site preparation activities for the				Avoid the removal of bat maternity habitat between April 15 and August 31	potential to adversely affect bats or	Geographic Extent: Level I		
construction of mine site infrastructure, the mine	•	_	_	during the construction phase, unless authorized under an <i>Endangered</i>	their habitat required to carry out the	Timing: Level I		
access road and the transmission line, ongoing				Species Act or other appropriate approval.	life processes necessary to survive and	Duration: Level III		
maintenance of the infrastructure, and the activities associated with final reclamation at closure.				Follow appropriate timing windows for vegetation removals; in combination	reproduce. There is no candidate hibernacula located in the Project	Frequency: Level I Reversibility: Level II		
associated with final recialifation at closure.	•	_	_	with timing windows for wildlife and wildlife habitat (6.12), Boreal Caribou	Development Area and therefore none	Reversibility. Level II		
				(6.13), Wolverine (6.14), and SAR birds (6.16), vegetation removals should	will not be impacted.			
-				only occur between September 15 to January 14.	With the implementation of mitigation			
		•	_	During construction and operation phases, avoid the removal / disturbance of foraging habitat within 2.6 km of candidate bat hibernacula, unless	measures, the residual effect is the			
	•	•		authorized under an <i>Endangered Species Act</i> or other appropriate approval.	removal of maternity roosting and			
				Undertake offsetting measures for bats such as establishing artificial	foraging bat habitat within the Project			
	•	•	•	hibernacula, as required by relevant <i>Endangered Species Act</i> approvals.	Development Area representing less			
				Implementation of mitigation measures for potential effects on wildlife and	than 1% of the available habitat in the			
	•	•	•	<ul> <li>wildlife habitat relevant to bats (Section 6.12.4) including:</li> <li>During construction of the Project, minimize the disturbance by using existing trails and roads for travel, where practical; and,</li> <li>During the operation phase of the transmission line, minimize vegetation</li> </ul>	regional study area. The residual effect is confined to the Project Development Area, occurs once during construction, and will occur outside			
				management to that necessary for safe operation.  Implementation of mitigation measures for potential effects on vegetation	sensitive periods bats. The residual will continue until post-closure but is			
	•	•	•	<ul> <li>During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and operation, minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs; and,</li> <li>During operation and closure phases, undertake progressive and final rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and wildlife habitat features including bats.</li> </ul>	partially reversible as site conditions within the Project Development Area will be altered until post-closure.			
	•	-	-	Develop a compact mine site to limit the areal extent of disturbance.	The change in the abundance and/or		Not significant	Moderate
				Co-locate the transmission line, airstrip and mine access road within a shared	distribution of bats and their habitats		-	
	•	_	_	infrastructure corridor, where feasible.	are not predicted to change the status			





		Phase <sup>1</sup>	l			Residual Adverse Effect(s)	dverse Effect(s)			
Potential Effect(s)	Con	do	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence		
Without mitigation, there may be a change in the function, connectivity, and quality of bat habitat during construction, operation and closure.	•	ı	ı	Avoid the removal of bat maternity habitat between April 15 and August 31 during the construction phase, unless authorized under an <i>Endangered Species Act</i> approval.	of populations or the availability of unique habitats, as the removed habitat types are abundant across the	Ecological and Social Context: Level I Magnitude: Level I				
This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the	•	•	ı	Maintain a 500 m radius of uncleared habitat around the entrance for confirmed bat hibernacula, unless otherwise authorized under an <i>Endangered Species Act</i> approval.	regional study area. With the implementation of mitigation measure, the indirect changes on the	Geographic Extent: Level I Timing: Level I Duration: Level II				
transmission line resulting in sensory disturbances from the use of equipment, the ongoing maintenance of the infrastructure resulting in	•	•	ı	During construction and operation phases, avoid the removal / disturbance of foraging habitat within 2.6 km of confirmed bat hibernacula, unless authorized under an <i>Endangered Species Act</i> approval.	function, connectivity and quality of wildlife habitat will result in a residual effect is predicted to be less than 1%	Frequency: Level II Reversibility: Level I				
sensory disturbances from vegetation management and the use of equipment, and the activities	•	•	•	Undertake offsetting measures for bats such as establishing artificial hibernacula, as required by relevant <i>Endangered Species Act</i> approvals.	of the available bat maternity and foraging habitat in the regional study					
and the use of equipment, and the activities associated with final reclamation at closure.	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on air quality relevant to bats (Section 6.2.4) including:         <ul> <li>During construction, operation and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul> </li> </ul>	area. The residual effect is confined to the local study area and occur intermittently throughout construction, operation and active closure, but is fully reversible at closure. With the implementation of timing windows, the timing of the residual effect will be low.					
	•	•	•	<ul> <li>Implement the mitigation measures for potential effects on noise relevant to bats (Section 6.3.4), including:         <ul> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible.</li> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills.</li> <li>Generator intakes and exhausts in the process plant will use silencers.</li> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions during all phases of the Project</li> </ul> </li> <li>Reversing alarms should be dimmable with white noise and/or strobe lights, but in accordance with the applicable health and safety regulations, during all phases of the Project</li> <li>The use of engine brakes will be prohibited.</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible, during all phases of the Project</li> <li>Regular inspections will take place to confirm that equipment and machinery used on site is operated in good working condition through regular maintenance.</li> </ul>						





		Phase <sup>1</sup>	l			Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	CI	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				For helicopter use during transmission line construction, minimum flight altitudes will be maintained unless the helicopters are engaged in construction tasks, landing or departure.				
	•	•	•	Implement mitigation measures for lighting to minimize sensory disturbance, including:  To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms; and Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practicable.				
	•	•	•	<ul> <li>Implement the mitigation measures for potential effects on surface water relevant to bats (Section 6.6.4, Section 6.7.4 and 6.8.4), including.</li> <li>During construction, operation and active closure, an erosion and sediment control plan will be implemented to manage runoff water in disturbed areas;</li> <li>During construction, operation and active closure, an integrated water management system will be designed to collect and control contact water;</li> <li>Water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system;</li> <li>Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures; and,</li> <li>Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements.</li> </ul>				
	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on vegetation communities and wetlands relevant to bats (Section 6.2.4) including:</li> <li>During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and safe operation;</li> <li>During construction and operation, minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs;</li> <li>During construction, operation and active closure phases, implement mitigation measures for wetlands; and,</li> <li>During operation and closure phases, undertake progressive and final rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and wildlife habitat features including bats.</li> </ul>				
	•	•	•	Implementation of mitigation measures for potential effects on wildlife and wildlife habitat relevant to bats (Section 6.12.4) including:				





	Phase <sup>1</sup>					Residual Adverse Effect(s)				
Potential Effect(s)	Con	do	IJ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence		
				<ul> <li>During construction of the Project, minimize the disturbance by using existing trails and roads for travel, where practical.</li> <li>During the operation phase of the transmission line, minimize vegetation management to that necessary for safe operation.</li> </ul>						
Without mitigation, there may be a change in the risk of mortality of bats during construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in the loss of habitat and the use of equipment, ongoing operation of the mine access road, and the activities associated with final reclamation at closure.	•	_	ı	Avoid the removal of bat maternity habitat between April 15 and August 31 during the construction phase, unless authorized under an <i>Endangered Species Act</i> approval.	The candidate hibernaculum is not located in the Project Development Area and noise from Project activities	Ecological and Social Context: Level   Magnitude: Level	Not significant	Moderate		
	•	•	-	Maintain a 500 m radius of uncleared habitat around the entrance for confirmed bat hibernacula, unless otherwise authorized under an Endangered Species Act approval.	is not expected to affect potential swarming or hibernating bats at Cliff 1 with mitigation.	Geographic Extent: Level   Timing: Level   Duration: Level				
	•	•	-	During construction and operation phases, avoid the removal / disturbance of foraging habitat within 2.6 km of confirmed bat hibernacula, unless authorized under an <i>Endangered Species Act</i> approval.	With implementation of mitigation measures, there may be a low	Frequency: Level I Reversibility: Level I				
	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on wildlife and wildlife habitat relevant to bats (Section 6.12.4) including:         <ul> <li>During construction, operation and closure phases of the Project, domestic solid waste products and similar materials will be properly secured, stored and disposed of at an offsite licensed facility, particularly anything that is an attractant for scavenging wildlife. Domestic solid waste products will be transported to a landfill off site, mitigating the habitat sink effect of increased predator densities that can be created due to access to landfill sites;</li> <li>During the operation phase of the mine access road, enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings;</li> <li>During the operation phase of the mine access road, Project-related vehicles travelling on the mine access road must come to a stop if wildlife is encountered and provide them with the right-of-way to cross the road;</li> <li>During construction, operation and closure phases, wildlife (including species at risk) awareness training will be provided to Project employees; and,</li> <li>During construction, operation and closure phases, log (and report as needed) observed wildlife, sign / tracks and wildlife-vehicle collisions and alter mitigation measures as appropriate.</li> </ul> </li> </ul>	potential for a change in the risk of mortality during construction and operational activities in previously undisturbed habitat. The residual effect is confined to the Project Development Area, and will occur during construction, operation and active closure, on an infrequent basis, and is fully reversible. With the implementation of timing windows, the timing of the residual effect will be low.					

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase	1	Table 13-13. 3AR bitus - Summary of Fotential Effects, Witagation, Res		Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	ס	Proposed Mitigation Measures	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>SAR Birds Valued Component (Section 6.16)</li> <li>Area of Federal Jurisdiction: Species at Risk</li> <li>Linkage from other VCs: Air Quality; Noise and V</li> <li>Linkage to other VCs: Commercial Land and Reserved</li> </ul>		_		n Communities and Wetlands Recreation; Traditional Land and Resource Use; Human and Ecological Health				
Without mitigation, there may be a change in the	•	•	_	Develop of a compact mine site to limit the areal extent of disturbance.	The change in SAR bird habitat	<b>Ecological and Social Context:</b>	Not Significant	Moderate
relative abundance of SAR bird habitat during				Co-locate the transmission line, airstrip and mine access road within a shared	meets the protection requirement	Level I		
construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line, ongoing maintenance of the infrastructure, and the activities				infrastructure corridor, where feasible.	of the Recovery Strategy for	Magnitude: Level I		
				Follow appropriate timing windows for vegetation removals; in combination	Eastern Whip-poor-will. Further,	Geographic Extent: Level I		
	•	•	_	with timing windows for wildlife and wildlife habitat (6.12), Boreal Caribou	there is sufficient SAR bird habitat	Timing: Level I		
				(6.13), Wolverine (6.14), and bats (6.15), vegetation removals should only	maintained elsewhere in the regional study area and there is a	Duration: Level III Frequency: Level I		
associated with final reclamation at closure.				occur between September 15 to January 14.  Avoid the removal of Category 1, 2 and 3 habitat for Eastern Whip-poor-will,	low potential to adversely affect	Reversibility: Level II		
•		•	_	unless authorized under an <i>Endangered Species Act</i> or other appropriate	SAR birds.	,		
				approval.	With the implementation of			
				Avoid the removal of nests for Barn Swallow, Eastern Whip-poor-will or Lesser	mitigation measures, there will be			
	•	•	_	Yellowlegs, unless authorized under an Endangered Species Act approval	less than a 1% direct loss of			
				and/or a permit issued under the Migratory Bird Regulations.	breeding habitat for Eastern Whip-			
				Implementation of mitigation measures for potential effects on vegetation	poor-will, Lesser Yellowlegs and Short-eared Owl in the regional			
				communities and wetlands relevant to SAR birds (Section 6.2.4) including:	study area. The residual effect is			
				During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the	confined to the Project			
				construction and safe operation;	Development Area, occurs once			
				<ul> <li>During construction and operation, minimize the removal of woody vegetation</li> </ul>	during construction, but the			
				within the transmission line corridor to maintain natural cover to adjacent	continues until rehabilitation			
	•	•	•	areas. The removal of woody vegetation will be limited to hazard trees and	measures have stabilized during			
				clearing to provide safe construction access and infrastructure needs; and,	the post-closure phase, when it will			
				During operations and closure phases, undertake progressive and final     which like the strength and t	be partially reversible. With the implementation of timing			
				rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation	windows, the timing of the residual			
				sources, incorporates plant species of interest to Indigenous communities, and	effect will be low.			
				wildlife habitat features.				
				Implementation of mitigation measures for potential effects on wildlife and wildlife				
				habitat relevant to SAR birds (Section 6.12.4) including:				
	•	•	_	During construction of the Project, minimize the disturbance by using existing				
				trails and roads for travel, where practical; and,				
				During the operation phase of the transmission line, minimize vegetation management to that necessary for safe operation.				
Without mitigation, there may be a change in the	•	_	_	Develop of a compact mine site to limit the areal extent of disturbance.	As there is sufficient SAR bird	Ecological and Social Context:	Not Significant	Moderate
function, connectivity, and quality of SAR bird				Co-locate the transmission line, airstrip and mine access road within a shared	habitat elsewhere in the regional	Level I		moderate
habitat during construction, operation and closure.	•	•	_	infrastructure corridor, where feasible.	study area, there is a low potential	Magnitude: Level I		
This is due to site preparation activities for the				Follow appropriate timing windows for vegetation removals; in combination	to adversely affect SAR birds and	Geographic Extent: Level I		
construction of mine site infrastructure, the mine	•	•	_	with timing windows for wildlife and wildlife habitat (6.12), Boreal Caribou	the habitat. Further, the indirect	Timing: Level II		





		Phase	1	Table 15-15: SAR Birds - Summary of Potential Effects, Mittigation, Res		Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
access road and the transmission line resulting in				(6.13), Wolverine (6.14), and bats (6.15), vegetation removals should only	effects will meet the requirements	Duration: Level II		
sensory disturbances, ongoing maintenance of the infrastructure resulting in sensory disturbances, and				occur between September 15 to January 14.  Avoid the removal of Category 1, 2 and 3 habitat for Eastern Whip-poor-will,	of the Recovery Strategy for Eastern Whip-poor-will habitat and	Frequency: Level III Reversibility: Level I		
the activities associated with final reclamation at closure.	•	•	_	unless authorized under an <i>Endangered Species Act</i> or other appropriate approval.	forest cover in the regional study area.	Reversibility. Lever		
	•	•	_	Avoid the removal of nests for Barn Swallow, Eastern Whip-poor-will or Lesser Yellowlegs, unless authorized under an <i>Endangered Species Act</i> approval	With the implementation of mitigation measure, the residual			
	•	•	•	<ul> <li>and/or a permit issued under the Migratory Bird Regulations.</li> <li>Implementation of mitigation measures for potential effects on air quality relevant to SAR birds (Section 6.2.4) including:         <ul> <li>During construction, operations and active closure, a dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed;</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants, if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads; and,</li> <li>Vehicle speeds will be limited.</li> </ul> </li> </ul>	effect is predicted to affect less than 1% of the available SAR bird habitat in the regional study area compared to baseline conditions. The residual effect is constrained within the LSA and will occur intermittently during construction, operation and active closure and may occur occasionally during sensitive periods for SAR birds.			
	•	•	•	<ul> <li>Implement the mitigation measures for potential effects on noise relevant to SAR birds (Section 6.3.4), including:</li> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible;</li> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills;</li> <li>Generator intakes and exhausts in the process plant will use silencers;</li> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions during all phases of the Project;</li> <li>Reversing alarms should be dimmable with white noise and/or strobe lights, but in accordance with the applicable health and safety regulations, during all phases of the Project;</li> <li>The use of engine brakes will be prohibited;</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible, during all phases of the Project;</li> <li>Regular inspections will take place to confirm that equipment and machinery used on site is operated in good working condition through regular maintenance; and,</li> <li>For helicopter use during transmission line construction, minimum flight altitudes will be maintained unless the helicopters are engaged in construction tasks, landing or departure.</li> </ul>				





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	•	<ul> <li>During construction, operation and closure phases, implement mitigation measures for lighting to minimize sensory disturbance (Appendix J), including:         <ul> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms; and,</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practicable.</li> </ul> </li> </ul>				
	•	•	•	<ul> <li>Implement the mitigation measures for potential effects on surface water relevant to SAR birds (Section 6.6.4, Section 6.7.4 and 6.8.4), including.</li> <li>During construction, operation and active closure, an erosion and sediment control (ESC) plan will be implemented to manage runoff water in disturbed area;</li> <li>During construction, operation and active closure, an integrated water management system will be designed to collect and control contact water;</li> <li>Water collection ditches will be constructed and operated around the perimeter of infrastructure, including the CDF and stockpiles to collect overland flow and seepage and direct it to the integrated water management system;</li> <li>Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures;</li> <li>Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements; and,</li> <li>Implement measures outlined in a spill prevention and contingency plan to be developed prior to construction.</li> </ul>				
	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on vegetation communities relevant to SAR birds (Section 6.2.4) including:         <ul> <li>During construction and operation, minimize the clearing of vegetation within the mine access road and transmission line corridor to that needed for the construction and safe operation;</li> <li>During construction and operation, minimize the removal of woody vegetation within the transmission line corridor to maintain natural cover to adjacent areas. The removal of woody vegetation will be limited to hazard trees and clearing to provide safe construction access and infrastructure needs; and,</li> <li>During operations and closure phases, undertake progressive and final rehabilitation of mine development in accordance with the filed Closure Plan, and implement a revegetation plan that preferentially uses local vegetation sources, incorporates plant species of interest to Indigenous communities, and wildlife habitat features.</li> </ul> </li> </ul>				
	•	•	_	<ul> <li>Implementation of mitigation measures for potential effects on wildlife and wildlife habitat relevant to SAR birds (Section 6.12.4) including:         <ul> <li>During construction of the Project, minimize the disturbance by using existing trails and roads for travel, where practical;</li> <li>Maintain existing hydroperiod conditions, outside the zone of influence for dewatering, by directing water from dewatering activities away from terrestrial habitats, where possible; and,</li> </ul> </li> </ul>				





		Phase	,1	Table 13-13. SAR Birds - Summary of Fotential Effects, Windgation, Res	Residual Adverse Effect(s)				
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
				During the operation phase of the transmission line, minimize vegetation management to that necessary for safe operation.					
Without mitigation, there may be a change in the risk of mortality of SAR birds during construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in the loss of habitat and the use of equipment, ongoing operation of the mine access road, and the activities associated with final reclamation at closure.	•	•	_	Follow appropriate timing windows for vegetation removals; in combination with timing windows for wildlife and wildlife habitat (6.12), Boreal Caribou (6.13), Wolverine (6.14), and bats (6.15), vegetation removals should only occur between September 15 to January 14.	With the implementation of mitigation measure, there may a minor residual effect due to the change in the risk of mortality for	Ecological and Social Context: Level   Magnitude: Level   Geographic Extent: Level	Not Significant	Moderate	
	•	•	-	Avoid the removal of Category 1, 2 and 3 habitat for Eastern Whip-poor-will, unless authorized under an ESA or other appropriate approval.	SAR bird species. The residual effects will be confined to the	Timing: Level I  Duration: Level III			
	•	•	-	Avoid the removal of nests for Barn Swallow, Eastern Whip-poor-will or Lesser Yellowlegs, unless authorized under an <i>Endangered Species Act</i> approval and/or a permit issued under the Migratory Bird Regulations.	Project Development Area, occurs infrequently during construction, operations and active closure, and	Frequency: Level I Reversibility: Level I			
	•	•	-	Comply with the requirements of the MBCA and Migratory Birds Regulations, if Barn Swallow, Eastern Whip-poor-will or Lesser Yellowlegs individuals are encountered during Project activities.	<b></b>				
		•	•	Implement the mitigation measures for potential effects on surface water relevant to SAR birds (Section 6.6.4, Section 6.7.4 and 6.8.4), including.  Implement measures outlined in a spill prevention and contingency plan to be developed prior to construction.	effect will be low.				
	•	•	•	<ul> <li>Implementation of mitigation measures for potential effects on wildlife and wildlife habitat relevant to SAR birds (Section 6.12.4) including:</li> <li>During construction, operation and closure phases of the Project, domestic solid waste products and similar materials will be properly secured, stored and disposed of at an offsite licensed facility, particularly anything that is an attractant for scavenging wildlife. Domestic solid waste products will be transported to a landfill off site, mitigating the habitat sink effect of increased predator densities that can be created due to access to landfill sites;</li> <li>Discouraging wildlife from inhabiting contact water ponds (including the codisposal facility and central water storage pond);</li> <li>During the operation phase of the mine access road, enforce reduced speed limits along Project-controlled roads within high-quality wildlife habitats, particularly along segments with known or recurrent wildlife crossings;</li> <li>During the operation phase of the mine access road, Project-related vehicles travelling on the mine access road must come to a stop if wildlife is encountered and provide them with the right-of-way to cross the road;</li> <li>During construction, operation and closure phases, wildlife (including SAR) awareness training will be provided to Project employees; and,</li> <li>During construction, operation and closure phases, log (and report as needed) observed wildlife, sign / tracks and wildlife-vehicle collisions and alter mitigation measures as appropriate.</li> </ul>					

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





	Pł	hase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	nment tion 6.3	that a 3), Fisl	re Di n anc	<b>17)</b> rectly Linked or Incidental to Areas of Federal Jurisdiction Fish Habitat (Section 6.10), Vegetation Communities and Wetlands (Sections 6.11), Wildlife	and Wildlife Habitat (Section 6.12)			
Without mitigation, there may be a change in forestry resources during construction, operation and closure.  This is due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line resulting in the loss of vegetation used for forestry.  Without mitigation, there may be a change in transping ability, including the associated experience.	•	_	_	<ul> <li>Limit the removal of merchantable timber through:</li> <li>Development of a compact mine site.</li> <li>Co-locating the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible</li> <li>Detailed engineering will be conducted to optimize the transmission line route</li> </ul>	With the implementation of mitigation measures, there is no residual effect due to changes in forestry resources during any phase of the Project.	Not applicable	Not applicable	High
	•		-	Prior to, and during construction, FMG will work with local forestry companies to salvage valued harvestable timber, and offering it to the forestry companies managing the two affected Forest Management Units.				
trapping ability, including the associated experience during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site	•	-	_	<ul> <li>Limit the loss and alteration of wildlife habitat through:</li> <li>Development of a compact mine site.</li> <li>Co-locating the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible</li> <li>Detailed engineering will be conducted to optimize the transmission line route</li> </ul>	Wildlife species that are trapped are relatively tolerant of sensory disturbance associated with human and infrastructure presence.	Ecological and Social Context: Level   Magnitude: Level   Geographic Extent: Level   Duration: Level	Not Significant	High
infrastructure, the mine access road and the transmission line.	•	-	-	<ul> <li>Detailed engineering will be conducted to optimize the transmission line route</li> <li>Implement the mitigation measures for reducing sensory disturbance (noise [Section 6.3], light) [Appendix J] including:</li> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible.</li> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills.</li> <li>Generator intakes and exhausts in the process plant will use silencers.</li> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions.</li> <li>Reversing alarms will be dimmable with white noise and/or strobe lights,</li> <li>The use of engine brakes will be prohibited.</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible.</li> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms.</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practical.</li> <li>Prior to and during construction, maintain active engagement with trappers regarding effects to commercial land and resource use, including engagement about access to resources.</li> <li>A controlled access gate is proposed to control unauthorized use of the mine access road.</li> </ul>	Although less than 10% of the habitat is affected, it is recognized that noise could have an effect on the experience of individual trappers; however, the degree to which avoidance may occur is subject to individual sensitivities and choices.  With the implementation of mitigation measures, the residual effect on trapping is a less than 10% change. The residual effect is constrained to the local study area, occurs continuously throughout construction, operation and active closure and will be partially reversible at post-closure as some areas of the Project Development Area will not be revegetated (i.e., co-disposal facility embankments).	Frequency: Level III Reversibility: Level II		
Without mitigation, there may be a change in commercial bait harvesting, including the	•	-	_	enhancements during construction and operation phases.  Limit the aerial extent of the Project and overprinting of bait harvesting areas through the development of a compact mine site.	There will be a minor reduction in the area available to bait harvesters;	Ecological and Social Context: Level	Not Significant	High





	ı	hase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	IJ	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
associated experience during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line.	•	•	•	<ul> <li>Implement the mitigation measures for reducing sensory disturbance (noise [Section 6.3], light) [Appendix J] including:</li> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible.</li> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills.</li> <li>Generator intakes and exhausts in the process plant will use silencers.</li> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions.</li> <li>Reversing alarms will be dimmable with white noise and/or strobe lights,</li> <li>The use of engine brakes will be prohibited.</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible.</li> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms.</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practical.</li> </ul>	however, additional habitat will be created once the dewatered basin is reconnected with the remainder of Springpole Lake.  With the implementation of mitigation measures, the residual effect on baitfish harvesting is less than 7% within the regional study area. The residual effect is constrained to the Project Development Area, occurs continuously through construction, operation and active closure, and will be fully reversible at closure.	Magnitude: Level I Geographic Extent: Level I Duration: Level III Frequency: Level III Reversibility: Level I		
	•	•	•	Install screens or use other measures at water intakes to prevent entrainment or impingement of fish as per the DFO Code of Practice (DFO 2020).				
	•	-	_	Keeping the dewatering (discharge to the downstream environment) to within the framework 10% of instantaneous flow so that the activity is not harmful to fish and fish habitat, and maintains downstream water quantity and flow within natural variation.				
	•	•	•	A controlled access gate is proposed to control unauthorized use of the mine access road.				
Without mitigation, there may be a change in outfitter camps, including the associated experience during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line.	•	•	•	<ul> <li>Implement the mitigation measures for reducing changes in the viewscape         (Appendix U), including:         <ul> <li>Development of a compact mine site.</li> <li>Co-locating the transmission line, airstrip and mine access road within a shared infrastructure corridor, where feasible.</li> <li>Preserving a tree line as a buffer around the mine site to diminish the amount of the mine site that can be seen.</li> </ul> </li> <li>This buffer around the Project will be maintained wide enough to withstand the loss of trees, such as toppled by wind.</li> <li>All buildings and facilities will be deconstructed and removed, and disturbed areas will be stabilized.</li> </ul>	With the implementation of mitigation measures, there is no residual effect due to changes in outfitter camps during any phase of the Project.	Not applicable	Not applicable	High
	•	•	•	<ul> <li>Implement the mitigation measures for reducing sensory disturbance (noise [Section 6.3], light) [Appendix J] including:         <ul> <li>Building dimensions, layout and orientation will be designed to shield noise sources, where possible.</li> <li>Acoustical enclosures will be used in the process plant to limit overall noise emissions from key noise sources, such as the ball mills.</li> <li>Generator intakes and exhausts in the process plant will use silencers.</li> </ul> </li> </ul>				





	P	nase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				<ul> <li>Motorized equipment will be selected or designed with mufflers / silencers to limit noise emissions.</li> <li>Reversing alarms will be dimmable with white noise and/or strobe lights,</li> <li>The use of engine brakes will be prohibited.</li> <li>Vehicles and equipment will be operated in such a way that impulsive noise is minimized, where possible.</li> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms.</li> <li>Minimize light spill and glare using shielding on stationary light sources and direct lighting downwards where practical.</li> </ul>				
	•	-	-	Prior to and during construction, maintain active engagement with Indigenous communities and outfitters regarding effects to commercial land and resource use, including engagement about access to resources.				
	•	•	•	A controlled access gate is proposed to control unauthorized use of the mine access road.				
Without mitigation, there may be a change in aggregate resources during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line.	•	_	_	Development of a compact mine site to limit the amount of aggregate material required for construction.	With the implementation of mitigation measures, there is no residual effect due to changes in aggregate resources during any phase of the Project.	Not applicable	Not applicable	High
Without mitigation, there may be a change in access to mineral claims during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line.	•	•	•	During all phases, FMG will work with mineral claim holders and regulators to accommodate access to mineral claims by claim holders and to secure permission to construct the transmission line on mineral claims held by others.	With the implementation of mitigation measures, there is no residual effect due to changes in access to mineral claims during any phase of the Project.	Not applicable	Not applicable	High

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase <sup>1</sup>				Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
Outdoor Recreation Valued Component (Section 6.	18)								
				that are Directly Linked or Incidental to Areas of Federal Jurisdiction					
Linkage from other VCs: Noise and vibration (Section 1)	tion 6	.3), Sur	face w	ater systems (Section 6.6 to 6.9), Fish and fish habitat (Section 6.10), Vegetation commun	ities and wetlands (Sections 6.11), Wild	llife and wildlife habitat (Section 6.	12)		
Linkage to other VCs: Local and regional economy					T	T.,	T		
Without mitigation, there may be a change in	•	•	•	Implement the mitigation measures for potential effects on noise (Section 6.3.4).	With the implementation of	Not applicable	Not applicable	High	
recreational fishing during construction, operation and closure.	•	•	•	Implement the mitigation measures for the potential effects on surface water (Section	mitigation measures, there is no				
This could occur due to the construction of the				6.6.4).	residual effect due to changes in recreational fishing during any				
dikes, the controlled dewatering of the open pit	•	•	•	Implement the mitigation measures for potential effects on fish and fish habitat	phase of the Project.				
basin and the operation of the mine site area that	•	<del> </del> _		(Section 6.10.4).  Minimize the Project footprint (areal extent).	phase of the Project.				
may change the experience of fishers.	_			Conduct progressive reclamation during operations and final reclamation during					
	_	•	•	closure to promote the reestablishment of wildlife and aquatic habitat.					
				Prohibit fishing and hunting within the controlled access portion of the Project					
	•	•	•	Development Area by Project personnel while working or residing on site.					
recreational hunting during construction, operation	•	•	•	Implement the mitigation measures for potential effects on noise (Section 6.3.4).	With the implementation of	Not applicable	Not applicable	High	
	_	_	_	Implement the mitigation measures for potential effects on wildlife and wildlife	mitigation measures, there is no				
and closure.	•	•	•	habitat (Section 6.12.4).	residual effect due to changes in				
This could occur due to the construction of the	•	_	_	Minimize the Project footprint (areal extent).	recreational hunting during any				
dikes, the controlled dewatering of the open pit	_	•		Conduct progressive reclamation during operations and final reclamation during	phase of the Project.				
basin and the operation of the mine site area that may change the experience of hunters.		<u> </u>		closure to promote the reestablishment of wildlife and aquatic habitat.					
may change the experience of numers.	•	•	•	Prohibit fishing and hunting within the controlled access portion of the Project					
				Development Area by Project personnel while working or residing on site.					
Without mitigation, there may be a change by users	•	•	•	Implement the mitigation measures for potential effects on air quality (Section 6.2.4).	With the implementation of	Not applicable	Not applicable	High	
of recreational areas during construction, operation and closure.	•	•	•	Implement the mitigation measures for potential effects on noise (Section 6.3.4).	mitigation measures, there is no residual effect due to changes in				
This could occur due to the construction of the mine	•	•	•	Implement the mitigation measures for the potential effects on surface water (Section 6.6.4).	recreational areas during any phase				
site infrastructure, mine access road and	•	_	_	Minimize the Project footprint (areal extent).	of the Project.				
transmission line, and the operation of the mine site area that may change the experience of recreational users.	•	•	•	<ul> <li>Implement mitigation for lighting and changes to viewscapes to minimize sensory disturbance, including:         <ul> <li>To prevent a direct line-of-sight from light, maintain light sources below natural barriers such as tree lines or artificial barriers such as berms;</li> <li>Minimize light spill and glare by through the use of shielding on stationary light sources and direct lighting downwards where practical; and,</li> <li>Preserve a tree line as a buffer to minimize the amount of the mine site that can be seen from recreational areas.</li> </ul> </li> </ul>					





		Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Without mitigation, there may be a change in navigation during construction, operation and	•	•	•	Implement the mitigation measures for the potential effects on surface water (Section 6.6.4).	With the implementation of mitigation measures, there is no	Not applicable	Not applicable	High
closure.	•	-	-	Minimize the Project footprint (areal extent).	residual effect due to changes in			
This could occur due to the construction of the dikes, and mine site area which may affect	•	•	_	Maintain alternate access to portages for navigation routes that traverse the Project Development Area during construction and operations phases; and	navigation during any phase of the Project.			
navigational routes during all phases.	_	1	•	Re-establish portage routes during the closure phase in a suitable location based on feedback from land and resource users.				
	•	•	•	Communicate Project activities affecting waterbodies/watercourse used for navigation throughout the construction, operation, and decommissioning/closure phases to potentially affected local resource users.				
	•	•	•	Post signage around the Project Development Area to alert local resource users of the presence of Project facilities and activities.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-18: Local and Regional Economy - Summary of Potential Effects, Mitigation, Residual Effects and Significance

Proposed Mitigation Measures <sup>2</sup> qualifications early and identify available training and training rs so local and Indigenous residents can acquire the necessary skills lify for potential Project employment.  se open job postings within the Indigenous communities as soon as active trecruiting programs as well as regular and effective outreach and	Description  With the proposed design and mitigation measures, an adverse negative residual effects due to	Characterization <sup>3</sup> Not applicable	Significance of Residual Adverse Effect  Not applicable	Prediction Confidence
qualifications early and identify available training and training rs so local and Indigenous residents can acquire the necessary skills lify for potential Project employment. See open job postings within the Indigenous communities as soon as	mitigation measures, an adverse	Not applicable	Not applicable	
rs so local and Indigenous residents can acquire the necessary skills lify for potential Project employment. se open job postings within the Indigenous communities as soon as	mitigation measures, an adverse	Not applicable	Not applicable	
	change in employment levels in		Not applicable	High
nications with Indigenous communities to support recruitment, go through the use of career fairs, information sessions, workshops, public factsheets, community meetings and any other measures that may awareness of and access to information on employment opportunities at eact—and associated education, training, skills and employment experience ments and opportunities.	municipalities are not predicted and therefore a determination of significance is not required.			
a Health and Wellness Strategy (Appendix Q-3) focused on employee health and wellness to complement health and safety programs and to local and Indigenous employees through the following: sideration for individuals in addiction treatment and their ongoing timent needs; asportation and logistics support to individuals accessing treatment grams; aborate with proximate communities in securing funding for employment diness programs, to be delivered by health care service providers and hers to prepare community members for Springpole Project opportunities, a focus on long-term operational phase employment; adatory diversity, cultural and gender sensitivity training for managers, ervisors and contractors; ite orientation for Indigenous cultural awareness content; incial wellness and literacy workshops; and employment incentives for women and youth; and dision of welcoming and safe environments, including mine sites and individuals complexes that comply with high standards of health and safety; as taken to help ensure the security and safety of women in mine odation; support given to provide cultural spaces for smudging, prayer for ceremonies; and the creation of washroom facilities for all genders.				
	ervisors and contractors; ite orientation for Indigenous cultural awareness content; incial wellness and literacy workshops; ining and employment incentives for women and youth; and ision of welcoming and safe environments, including mine sites and odations complexes that comply with high standards of health and safety; is taken to help ensure the security and safety of women in mine odation; support given to provide cultural spaces for smudging, prayer or ceremonies; and the creation of washroom facilities for all genders. In opportunity to form one or more Human Resources Committees with the participating Indigenous communities.	ervisors and contractors; ite orientation for Indigenous cultural awareness content; incial wellness and literacy workshops; ining and employment incentives for women and youth; and ision of welcoming and safe environments, including mine sites and odations complexes that comply with high standards of health and safety; is taken to help ensure the security and safety of women in mine odation; support given to provide cultural spaces for smudging, prayer for ceremonies; and the creation of washroom facilities for all genders. In opportunity to form one or more Human Resources Committees with the participating Indigenous communities. Indiditional coaching and mentoring for advancement to senior,	ervisors and contractors; ite orientation for Indigenous cultural awareness content; incial wellness and literacy workshops; ining and employment incentives for women and youth; and ision of welcoming and safe environments, including mine sites and odations complexes that comply with high standards of health and safety; is taken to help ensure the security and safety of women in mine odation; support given to provide cultural spaces for smudging, prayer or ceremonies; and the creation of washroom facilities for all genders. In opportunity to form one or more Human Resources Committees with the participating Indigenous communities.	ervisors and contractors; ite orientation for Indigenous cultural awareness content; incial wellness and literacy workshops; ining and employment incentives for women and youth; and ision of welcoming and safe environments, including mine sites and odations complexes that comply with high standards of health and safety; is taken to help ensure the security and safety of women in mine odation; support given to provide cultural spaces for smudging, prayer or ceremonies; and the creation of washroom facilities for all genders. In opportunity to form one or more Human Resources Committees with the participating Indigenous communities. Indiditional coaching and mentoring for advancement to senior,





# Table 15-18: Local and Regional Economy - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				development, and who have demonstrated a likelihood to succeed in such development.				
	•	•	-	Share information about employment preparation and training with Indigenous communities, non-Indigenous organizations and educational institutions.				
	•	•	•	Establish a skills inventory and local and Indigenous business inventory that are updated and retained until the active closure phase.				
	_	_	•	Provide job search assistance to employees at the closure phase.				
	•	•	_	Provide onsite accommodations that are safe and welcoming for the Project				
	•	•	_	workforce during the construction and operations phases.  Use a rotational workforce for the construction and operation of the Project to				
	•	•	•	support the employment of local and regional workers.  Provide bus transportation for employees to the worksite from a centralized				
	•	•	•	location to facilitate the employment of local and regional workers.  Give preference to Indigenous communities and local municipalities in hiring Project employees.				
	•	•	-	Communicate Project schedule, labour demand and potential sources with local municipalities for housing planning purposes.				
Change in labour income during construction, operation and closure due to Project employment	•	•	•	Establish a skills inventory and local and Indigenous business inventory that are updated and retained until the active closure phase.	With the proposed design and mitigation measures, an adverse	Not applicable	Not applicable	High
and expenditures.	•	•	-	Provide onsite accommodations that are safe and welcoming for the Project workforce during the construction and operations phases.	negative residual effect due to change in labour income is not predicted and			
	•	•	-	Use a rotational workforce for the construction and operation of the Project to support the employment of local and regional workers.	therefore a determination of significance is not required.			
	•	•	•	Provide bus transportation for employees to the worksite from a centralized location to facilitate the employment of local and regional workers.				
	•	•	•	Give preference to Indigenous communities and local municipalities in hiring Project employees.				
Change in business opportunities during construction, operation and closure due to Project employment and expenditures.	•	•	_	Work with local and Indigenous businesses to enhance the opportunity to participate in the supply of goods and services for construction and operations (e.g., facilitate workshops about opportunities available, collaborate with small businesses to prepare bids in response to requests for proposal, provide business education).	With the proposed design and mitigation measures, an adverse negative residual effect due to change in business opportunities is not predicted and therefore a	Not applicable	Not applicable	High
	•	•	•	Give preference to contracting for goods and services from the businesses in the Indigenous communities and local municipalities.	determination of significance is not required.			
Change in business income during construction, operation and closure due to Project employment and expenditures.	•	•	-	Work with local and Indigenous businesses to enhance the opportunity to participate in the supply of goods and services for construction and operations (e.g., facilitate workshops about opportunities available, collaborate with small businesses to prepare bids in response to requests for proposal, provide business education).	With the proposed design and mitigation measures, an adverse negative residual effect due to change in business income is not predicted and therefore a determination of	Not applicable	Not applicable	High
	•	•	•	Give preference to contracting for goods and services from the businesses in the Indigenous communities and local municipalities.	significance is not required.			





## Table 15-18: Local and Regional Economy - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	G	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	•	Establish and maintain a process to track local and regional contracting, subcontracting and procurement opportunities.				
Change in demand for training during construction, operation and closure due to Project employment and expenditures.	•	•	_	Post job qualifications early and identify available training and training providers so local and Indigenous residents can acquire the necessary skills and qualify for potential Project employment.	With the proposed design and mitigation measures, an adverse negative residual effect due to change	Not applicable	Not applicable	High
	•	•	-	Support processes and initiatives related to employment readiness, training and educational initiatives with Indigenous communities.	in demand for training is not predicted and therefore a determination of			
	•	•	_	Communicate employment skills requirements to local training providers to plan appropriate Project-related training; participate in the development of training programs to inform needs.	significance is not required.			
	•	•	-	Work with local communities to develop training programs oriented to operational needs.				
	•	•	•	Share information regarding available funding programs and provide support for applications, as feasible.				
	•	•	•	Share information about employment preparation and training with Indigenous communities, non-Indigenous organizations and educational institutions.				
	_	•	•	Support retraining programs to establish transferable skills for employees during the latter part of the operations phase.				
Change in government revenues during construction, operation and closure due to Project	•	•	•	Give preference to Indigenous communities and local municipalities in hiring Project employees.	With the proposed design and mitigation measures, an adverse	Not applicable	Not applicable	High
employment and expenditures.	•	•	-	Work with local and Indigenous businesses to enhance the opportunity to participate in the supply of goods and services for construction and operations (e.g., facilitate workshops about opportunities available, collaborate with small businesses to prepare bids in response to requests for proposal, provide business education).	negative residual effect due to change in government revenues is not predicted and therefore a determination of significance is not required.			
	•	•	•	Give preference to contracting for goods and services from the businesses in the Indigenous communities and in local municipalities.				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-19: Local and Regional Infrastructure and Services - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	ı		Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul> <li>Local and Regional Infrastructure and Services Value</li> <li>Area of Federal Jurisdiction: Indigenous people; C</li> <li>Linkage from other VCs: Local and Regional Econol</li> <li>Linkage to other VCs: none</li> </ul>	hange	in the	Envir	Section 6.20)  onment that are Directly Linked or Incidental to Areas of Federal Jurisdiction				
Without mitigation, there may be a change in the demand for educational services during construction, operation and closure.	•	•	-	Communicate employment skill requirements to local education / training providers during construction and operations to facilitate planning for appropriate Project-related training.	The residual effect on education is limited to the demand for employment-related training and will	Magnitude: Level   Geographic Extent: Level   Duration: Level	Not Significant	High
construction and operation of mine site infrastructure, the mine access road and the transmission line.	_	•	•	Support education and training programs for workers.  Support re-training of employees to establish transferable skills, in the latter portion of the operations phase to reduce adverse impacts on employment levels at closure.	be within existing capacity of education providers. With the implementation of mitigation measures, the residual effect will be low, localized, and will occur once during construction, operation and active closure. It will be fully reversible at closure.	Frequency: Level I Reversibility: Level I		
Without mitigation, there may be a change in the demand for housing during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the	•	•	-	Provide onsite accommodations for the Project workforce during construction and operations phases to minimize daily commuting from local communities.	With the proposed design and mitigation measures, a residual effect due to change in demand for housing	Not applicable	Not applicable	High
	•	•	_	Construct and operate the Project with a rotational workforce which reduces the need for Project workers to move to the local communities for employment as well as potential impacts on roads from daily commuting.	is not predicted and therefore a determination of significance is not required.			
transmission line.	•	•	•	Implement preferential hiring of employees from the local municipalities during all phases to provide local employment and labour income and to reduce potential in-migration and potential additional demands on infrastructure and services.				
	•	•	ı	Communicate Project schedule, labour demand and potential sources with local municipalities during construction and operations phases for housing planning purposes.				
		•	•	Support education and training programs for workers.  Support re-training of employees to establish transferable skills, in the latter portion of the operations phase to reduce adverse impacts on employment levels at closure.				
Without mitigation, there may be a change in the demand for emergency services, municipal services and infrastructure during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the transmission line.	•	•	•	Construct a helipad on site to support emergency transportation of personnel and to support field investigations. A small airstrip will be constructed to transport personnel on an infrequent basis. These would reduce road traffic to the Project Development Area.	services resulting from the disposal of Project non-recyclable waste material and demand for emergency services,	Magnitude: Level   Geographic Extent: Level   Duration: Level    Frequency: Level	Not Significant	High
	•	•	•	Implement preferential hiring of employees from the local municipalities during all phases to provide local employment and labour income and to reduce potential in-migration and potential additional demands on infrastructure and services.	will be within available facility capacities. With the implementation of mitigation	Reversibility: Level I		
	•	•	-	Maintain communications with relevant agencies and organizations during construction and operations to facilitate management of Project-related implications for services and infrastructure.	measures, the residual effect will be low, localized, and will occur continuously during construction,			





# Table 15-19: Local and Regional Infrastructure and Services - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	•	<ul> <li>Implement a Health and Wellness Strategy for Project employees which will, in part, contribute to management of demands on infrastructure and services in the municipalities and Indigenous communities. The Health and Wellness Strategy priorities are to:         <ul> <li>Establish and promote a workplace culture of positive employee health and well-being;</li> <li>Invest in meaningful and proactive employee health and wellness initiatives;</li> <li>Participate with health service providers towards addressing the major health &amp; wellness challenges facing northern and Indigenous peoples; and,</li> <li>Encourage and support employees to develop and maintain healthy lifestyles and habits, including related to mental health and wellbeing.</li> </ul> </li> </ul>	operation and active closure. It will be fully reversible at closure.			
	•	•	•	Have Project-rescue vehicles and trained First Responders on site during all phases to reduce potential demands for emergency services.  Control access to the mine site and employ onsite security staff during all Project				
		•	_	phases to reduce potential demands on emergency services.  Provide power for the Project operations through a connection to the Wataynikaneyap 230 kV line to reduce demand on local municipal utilities.				
	•	•	•	Construct a water treatment and sewage treatment system at the Project site to minimize demands on municipal services.				
	•	-	•	Develop cooperative protocols with responsible parties to provide temporary construction and closure phase workers access to emergency and medical services.				
Without mitigation, there may be a change in the demand for municipal and provincial community resources during construction, operation and	•	•	•	Implement preferential hiring of employees from the local municipalities during all phases to provide local employment and labour income and to reduce potential in-migration and potential additional demands on infrastructure and services.	With the proposed design and mitigation measures, a residual effect due to change in the demand for	Not applicable	Not applicable	High
closure.  This is due to site preparation activities for the construction and operation of mine site	•	•	_	Maintain communications with relevant agencies and organizations during construction and operations to facilitate management of Project-related implications for services and infrastructure.	municipal and provincial community resources are not predicted and therefore a determination of			
infrastructure, the mine access road and the transmission line.	•	_	•	Develop cooperative protocols with responsible parties to provide temporary construction and closure phase workers access to emergency and medical services.	significance is not required.			
	•	•	•	<ul> <li>Implement a Health and Wellness Strategy for Project employees which will, in part, contribute to management of demands on infrastructure and services in the municipalities and Indigenous communities. The Health and Wellness Strategy priorities are to:         <ul> <li>Establish and promote a workplace culture of positive employee health and well-being.</li> <li>Invest in meaningful and proactive employee health and wellness initiatives.</li> <li>Participate with health service providers towards addressing the major health &amp; wellness challenges facing northern and Indigenous peoples.</li> <li>Encourage and support employees to develop and maintain healthy lifestyles and habits, including related to mental health and wellbeing.</li> </ul> </li> </ul>				





## Table 15-19: Local and Regional Infrastructure and Services - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	l			Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	Cl	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Without mitigation, there may be a change in the demand on transportation networks during construction, operation and closure.  This is due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the	•	•	1	Provide onsite accommodations for the Project workforce during construction and operations phases to minimize daily commuting from local communities.	The residual effect on the demand on transportation due to increased road traffic will be within available	Magnitude: Level   Geographic Extent: Level   Duration: Level	Not Significant	High
	•	•	-	Construct and operate the Project with a rotational workforce which reduces the need for Project workers to move to the local communities for employment as well as potential impacts on roads from daily commuting.	capacities. With the implementation of mitigation measures, the residual effect will be	Frequency: Level III Reversibility: Level I		
transmission line.	•	•	•	Provide bus transportation to the worksite for the employees from a centralized location(s) to reduce traffic and minimize daily commuting.	low, localized, and will occur continuously during construction,			
	•	•	•	Construct a helipad on site to support emergency transportation of personnel and to support field investigations. A small airstrip will be constructed to transport personnel on an infrequent basis. These would reduce road traffic to the PDA.	operation and active closure. It will be fully reversible at closure.			
	•	•	_	Communicate schedule for major equipment delivery and removal with relevant local communities to manage impacts on municipal traffic.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	CI	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
<ul><li>6.12), Species at Risk (Section 6.13, Section 6.14 at Linkage to other VCs: Archaeology (Section 6.22)</li></ul>	, Noise and Sec	and Vib	ration 6)	(Section 6.3), Surface Water Systems (Section 6.6 to Section 6.9), Fish and Fish Habitat (Section 6.23), Human and Ecological Health (Section 6.24)				
Without mitigation, there may be a change in availability, access to and experience related to traditional terrestrial wildlife harvesting (hunting	•	_	_	Development of a compact mine site to limit the extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake	The habitat for species harvesting for hunting and trapping are common throughout the local and	Ecological and Social Context: Level    Magnitude: Level	Not Significant	Moderate
closure.  This could occur due to site preparation activities for the construction and operation of mine site infrastructure, the mine access road and the	•	•	•	Maintain Project designs such that no new public access points are developed on Springpole Lake	regional study area, and the removal of habitat in the Project	Geographic Extent: Level I  Duration: Level III		
	•	•	•	Maintain treed buffers between Project infrastructure and waterbodies to reduce visual disturbance  Building dimensions, layout and orientation will be designed to shield noise	Development Area is unlikely to affect the availability of traditional wildlife harvesting opportunities.	Frequency: Level I Reversibility: Level II		
	•	•	-	sources, where possible  Implement the mitigation measures for: Air quality including for dust	With the implementation of mitigation measures, the residual			
	•	•	•	(Section 6.2.4); Noise and vibration (Section 6.3.4); Vegetation communities and wetlands (Section 6.11.4); and, Wildlife and wildlife habitat (Section 6.12.4).	effect on traditional wildlife harvesting is a minor and localized loss of 3 ha of habitat for furbearers			
	•	•	•	Engage Indigenous environmental monitors from local communities in the implementation of mitigation and monitoring measures.	and overprinting of 478 ha of habitat for large mammals in the			
	•	•	•	<ul> <li>Prior to construction, establish Environmental Committee(s)to:</li> <li>Facilitate communications and meaningful engagement during construction, operation and closure of the Project;</li> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate environmental information, review Project approvals and environmental management and monitoring plans, participate in adaptive management and identify mitigation measures, address emerging issues and areas of interest identified by communities.</li> </ul>	Project Development Area. The residual effect is constrained to the Project Development Area, occurs once during construction and is expected to be partially reversible at post-closure as some areas of the Project Development Area will not be revegetated (i.e., co-disposal facility embankments).			
	•	-	_	Local Indigenous communities and identified points of reception will be advised ahead of transmission line construction work periods and as the construction work proceeds.	,			
	•	-	-	Work with local Indigenous communities to coordinate construction activities related to the transmission line to minimize overlap with the timing of traditional land use activities (e.g., fall moose hunt) and other sensitive periods.				
	•	•	•	Support the development and delivery of Indigenous led ceremonies on site to pay respect to the land air, and water prior to construction and at other key Project milestones				
	•	•	•	Facilitate the development and implementation of community-based monitoring programs to supplement (not duplicate) regulatory monitoring requirements  Support community land-based cultural activities.				
				1 Depper Deministry land based carrain detivities.		L		





		Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	•	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities.				
				Prior to construction, develop an access management strategy with local				
	•	•	•	Indigenous communities to manage access along the mine access road with				
				the purpose of supporting TLRU access and minimizing new public access				
				Maintain regular communication with trapline holders SL197 and SL 200				
	_	•	•	regarding activities and opportunities to facilitate their land use activities				
				Prior to construction, establish the alternate navigation route identified to maintain				
	•	•	•	access between Springpole Lake and Birch Lake, and maintain the alternate route				
				until post closure when the existing portage has been re-established				
	•	•	•	Hunting and fishing at the Project will be prohibited by employees and				
				contractors while at site, during all phases				
				Undertake revegetation in the mine site area, where practical, and include input from Indigenous communities and traditional land and resource use planning				
	•	•	_	documents.				
				Continue to participate in the Environmental Committee(s)at a rate commensurate				
	_	_	•	with activity in the Project Development Area.				
	•	•	•	Support reasonable community-based engagement and cultural activities.				
				Work with MNR and trapline license holders to determine alternative options				
	•	•	_	for trapline losses during construction and operation phases.				
	•	•	•	Achieve overall benefit requirements for Caribou (Section 6.13.4)				
Without mitigation, there may be a change in the				Development of a compact mine site to limit the extent of disturbance including a	The reduction of fish habitat is 6%	Ecological and Social Context:	Not Significant	Moderate
availability, access to and experience related to	•	_	-	mine footprint of 867 ha including minimizing the open pit mining area to 6% of	of the surface area of Springpole	Level II		
traditional aquatic wildlife harvesting (fishing)				Springpole Lake	Lake and the harvested fish species	Magnitude: Level I		
during construction, operation and closure.	•	•	•	Maintain Project designs such that no new public access points are developed	are common elsewhere in	Geographic Extent: Level I  Duration: Level III		
This could occur due to site preparation activities				on Springpole Lake  Maintain treed buffers between Project infrastructure and waterbodies to reduce	Springpole Lake and elsewhere in the local and regional study area	Frequency: Level I		
for the construction of the dike, controlled	•	•	•	visual disturbance	and removal of fish habitat from	Reversibility: Level I		
dewatering of the open pit basin, the operation of				Implement the mitigation measures for: Noise and vibration (Section 6.3.4);	within the Project Development			
mine site infrastructure, and during final	•	•	•	Surface water (Section 6.6.4, Section 6.7.4 and Section 6.8.4); and, Fish and	Area is unlikely to affect the			
reclamation activities, including the refilling of the				fish habitat (Section 6.10.4).	availability of fish harvesting areas.			
open pit basin.				Prior to construction, establish Environment Committee(s) and offer	With the implementation of			
				opportunities to participate to members of proximate Indigenous	mitigation measures, the residual			
				communities during the construction, operation and closure of the Project.	effect on traditional fish harvesting			
				The environment committee(s) aims to:	is a localized loss of 156 ha of fish			
	•			Facilitate communications and meaningful engagement during construction,      Projects	habitat, totaling 6% of the surface area of Springpole Lake in the			
		•	•	<ul> <li>operation and closure of the Project;</li> <li>Facilitate the use of Traditional knowledge in Project-related activities during</li> </ul>	Project Development Area. The			
				construction, operation and closure of the Project; and,	residual effect is constrained to the			
				<ul> <li>Share and evaluate environmental information, review Project approvals and</li> </ul>	Project Development Area, occurs			
				environmental management and monitoring plans, participate in adaptive	once during construction and is			
				management and identify mitigation measures, address emerging issues and				
				areas of interest identified by communities.				





		Phase <sup>1</sup>	1		Residual Adverse Effect(s)				
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
	•	•	•	Support community land-based traditional cultural activities.					
	•	•	•	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities.					
	•	_	_	Where there is interest, provide opportunities to local Indigenous communities and traditional land users to harvest plants and aquatic resources within the Project Development Area prior to construction.					
				Support the development and delivery of Indigenous led ceremonies on site to pay respect to the land air, and water prior to construction and at other key Project milestones.					
				Facilitate the development and implementation of community-based monitoring programs to supplement (not duplicate) regulatory monitoring requirements					
	•	•	•	Prior to construction, develop an access management strategy with local Indigenous communities to manage access along the mine access road, during construction, operation and closure phases of the Project, with the purpose of supporting traditional land and resource use access and minimizing new public access.					
				Prohibit fishing and hunting within the controlled access portion of the Project Development Area by Project personnel while working or residing on site.					
	_	-	•	Continue to participate in the Environment Committee(s) at a rate commensurate with activity in the Project Development Area.					
	_	•	_	Prior to closure, develop and implement a Lake Sturgeon reintroduction and restoration program harmonizing with the interest of local Indigenous communities and MNR.					
	•	•	•	Achieve fish habitat offsetting objectives (Appendix F).					
Without mitigation, there may be a change in availability, access to and experience related to traditional terrestrial traditional plant (food and	•	-	-	Development of a compact mine site to limit the extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake	The plants species harvested are common throughout the local and regional study areas, and therefore,	Ecological and Social Context: Level II Magnitude: Level I	Not Significant	Moderate	
medicinal) during construction, operation and closure. This could occur due to site preparation activities	•	•	•	Implement the mitigation measures for: Air quality including for dust (Section 6.2.4); Noise and vibration (Section 6.3.4); Surface water (Section 6.6.4); and, Vegetation communities and wetlands (Section 6.11.4).	removal in the Project Development Area is unlikely to affect the availability of traditional plant	Geographic Extent: Level   Duration: Level     Frequency: Level			
for the construction and operation of mine site infrastructure, the mine access road and the	•	•	•	Engage Indigenous environmental monitors from local communities in the implementation of mitigation and monitoring measures.	harvesting opportunities.	Reversibility: Level II			
transmission line, and during final reclamation activities.	•	•	•	<ul> <li>Prior to construction, establish Environment Committee(s) and offer opportunities to participate to members of proximate Indigenous communities during the construction, operation and closure of the Project.</li> <li>The environment committee(s) aims to:         <ul> <li>Facilitate communications and meaningful engagement during construction, operation and closure of the Project;</li> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate environmental information, review Project approvals and environmental management and monitoring plans, participate in adaptive</li> </ul> </li> </ul>	With the implementation of mitigation measures, the residual effect on traditional plant harvesting is a loss of 1,358 ha of vegetation communities and a loss of 352 ha of wetland communities in the Project Development Area. The residual effect is constrained to the Project Development Area, occurs once during construction				





		Phase <sup>1</sup>	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				management and identify mitigation measures, address emerging issues and areas of interest identified by communities.	and is expected to be partially reversible at post-closure as some			
	•	_	_	Work with local Indigenous communities to coordinate construction activities related to the transmission line to minimize overlap with the timing of traditional land use activities (e.g., fall moose hunt) and other sensitive periods.	areas of the Project Development Area will not be revegetated (i.e., co-disposal facility embankments).			
	•	•	•	Support community land-based traditional cultural activities.	· · · · · · · · · · · · · · · · · · ·			
	•	•	•	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities.				
	•	_	_	Where there is interest, provide opportunities to local Indigenous communities and traditional land users to the harvest plants and aquatic resources within the Project Development Area prior to construction.				
	•	•	•	Prior to construction, develop an access management strategy with local Indigenous communities to manage access along the mine access road, during construction, operation and closure phases of the Project, with the purpose of supporting TLRU access and minimizing new public access.				
	•	•	•	Support the development and delivery of Indigenous led ceremonies on site to pay respect to the land air, and water prior to construction and at other key Project milestones.				
	•	•	_	Facilitate the development and implementation of community-based monitoring programs to supplement (not duplicate) regulatory monitoring requirements.				
	•	•	_	Undertake revegetation in the mine site area, where practical, and include input from Indigenous communities and TLRU planning documents.				
	_	-	•	Continue to participate in the Environment Committee(s) at a rate commensurate with activity in the Project Development Area.				
Without mitigation, there may be a change in availability, access to and experience related to habitation, and use of spiritual or cultural sites	•	_	_	Development of a compact mine site to limit the extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake.	With the proposed design and mitigation measures, residual effects due to change in availability,	Not applicable	Not applicable	Moderate
during construction, operation and closure. This could occur due to site preparation activities	•	•	•	Maintain Project designs such that no new public access points are developed on Springpole Lake.	access to and experience related to habitation, and use of spiritual or			
for the construction and operation of mine site infrastructure, the mine access road and the	•	•	•	Maintain treed buffers between Project infrastructure and waterbodies to reduce visual disturbance.	cultural sites are not predicted and therefore a determination of			
transmission line, and during final reclamation activities.	•	•	_	Building dimensions, layout and orientation will be designed to shield noise sources, where possible.	significance is not required.			
	•	•	•	Implement the mitigation measures for: Noise and vibration (Section 6.3); Archaeology (Section 6.23); and, Cultural heritage (Section 6.24).				
	•	•	•	Engage Indigenous environmental monitors from local communities in the implementation of mitigation and monitoring measures.				
	•	•	•	Prior to construction, establish Environment Committee(s) and offer opportunities to participate to members of proximate Indigenous communities during the construction, operation and closure of the Project.  The environment committee(s) aims to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project;				





		Phase <sup>1</sup>				Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				<ul> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate environmental information, review Project approvals and environmental management and monitoring plans, participate in adaptive management and identify mitigation measures, address emerging issues and areas of interest identified by communities.</li> </ul>				
	•	ı	_	Support the development and delivery of Indigenous led ceremonies on site to pay respect to the land air, and water prior to construction and at other key Project milestones				
	•	ı	_	Local Indigenous communities and identified points of reception will be advised ahead of transmission line construction work periods and as the construction work proceeds.				
	•	I	l	Work with local Indigenous communities to coordinate construction activities related to the transmission line to minimize overlap with the timing of traditional land use activities (e.g., fall moose hunt) and other sensitive periods				
	•	•	•	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities.				
	•	•	•	Prior to construction, develop an access management strategy with local Indigenous communities to manage access along the mine access road, during construction, operation and closure phases of the Project, with the purpose of supporting traditional land and resource use access and minimizing new public access.				
	•	•	•	Prior to construction, establish the alternate navigation route identified to maintain access between Springpole Lake and Birch Lake, and maintain the alternate route until post closure when the existing portage has been reestablished				
	-	-	•	Continue to participate in the Environmental Committee(s) at a rate commensurate with activity in the Project Development Area.				

<sup>1</sup> Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

<sup>2</sup> Bolded text indicates a key mitigation measure.

<sup>3</sup> Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





Potential Effect(s)  By B			Phase	1		R	esidual Adverse Effect(s)		
Induge from ther VCS: Traditional Land and Resource use (Section 6.23)  White the major there may be direct or indirect land discutrances or removal of archaeological arrifacts, such as Indigenous material culture (e.g., lithics, operation and closure.  This could occur due to ground disturbances during preparation activities within the Project.  Development Area.    V   V   V   V   V   V   V   V   V	Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Residual	
Inhage from other VCs. Traditional Land and Resource Use (Section 6.23)      Without mitigation, there may be direct or indirect land disturbances or removal of archaeological resources from original context during construction, operation and closure.  This could occur due to ground disturbances during site preparation activities within the Project  Development Area.    Not applicable   Not applicable   Not applicable   Not applicable   Pligh	Archaeology Valued Component (Section 6.22)					<u> </u>		•	
Mithout mitigation, there may be direct or indirect land disturbances or removal of archaeological resources from original context during construction, operation and closure.  This could accur due to ground disturbances during ster preparation activities within the Project  Development Area.  Development Area.  Procedure (Appendix 5-6) will be intelled and activation phase, a Chance Find Procedure (Appendix 5-6) will be intelled and activation phase)  If thank remove and a construction destruction and operation. Staff training will also include a birt left story of the potential and documented infloration and occupation of the PDy and LSA.  If chance finds or deeply buried archaeological resources (including paleontological resources) will be intelled and all activities impacting the affected archaeological resources will cease immediately. A Itemsed a challenge of the sense immediately and the local police and coroner will be construction, and activation Heritage Act and the Standards and Guidelines for Consultant Archaeologists (IKCM 2011).  If human remains are associated with archaeologistic lists will be secured.  The MCM will be motified and all activities will cease immediately and the local police and coroner will be construction, and activate will also be notified to help protect against the site being subject to further alterations.  Prior to construction, a Environment Communities of will be established and poperturities to participate offered to members of prostruction to protect against the site being subject to prostruction to protect against the site being subject to prostruct to prostruct to prostruct to prostruct to prostruct to protect against the site being subject to prostruct to prostruct to prostruct to prostruct to protect against the site being subject to prostruct to pr									
Withour mitigation, there may be direct or indirect land disturbances or removal of archaeological arresources from onlyinal context during construction, operation and closure.  **Provided occur due to ground disturbances during ste preparation activities within the Project  Development Area.  **Provided occur due to ground disturbances during ste preparation activities within the Project  Development Area.  **Provided occur due to ground disturbances during ste preparation activities within the Project  Development Area.  **Provided occur due to ground disturbances during ste preparation activities within the Project  Development Area.  **Provided occur due to ground disturbances during ste preparation activities within the Project  Development Area.  **Provided occur due to ground disturbances during paleontological resources in organic deposits beneath lakes, marshes and peat) are neurotreed during the construction plant activities impacts the construction plant activities impacts will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be implemented and the site will be secured.  **Provided occur (Appendix S-6) will be ontacted. In situations where human remains are associated with archaeological resources will case summediately and the local policie and conserve will be cont	Linkage from other VCs: Traditional Land and Research	ource	Use (S	ection	6.21)				
land disturbances or removal of archaeological resources from original context during construction, operation and closure.  Paresources from original context during construction, operation and closure.  This could occur due to ground disturbances during stite preparation activities within the Project.  Development Area.    Paresource   Pares	Linkage to other VCs: Built Heritage Resources and	d Cult	tural H	eritage					
resources from original context during construction, operation and closure.  This could occur due to ground disturbances during site preparation activities within the Project Development Area.    Variable   Va					1 .		Not applicable	Not applicable	High
operation and closure.  This could occur due to ground disturbances during site preparation activities within the Project Development Area.  Development Area.  I change in the overent that chance finds are made during Project construction and operation. Staff training will also include a brief history of the potential and documented historical use and occupation of the PDA and LSA.  If chance finds or deeply buried archaeological resources (including paleontological resources in organic deposits beneath lakes, marshes and paet) are encountered during the construction phase, a Chance Find Procedure (Appendix S-6) will be implemented and the site will be secured. The MCM will be notified and all activities and the Standards and Guidelines for Consultant Archaeologists will carry out an archaeological assessment following the Ontatro Hertogae Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contified resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Constructed) in situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, operation and closure of the Project. The Environment Committee (s) will be an Environment Committee (s) will be a stabilished and opportunities during the construction, operation and closure of the Project. The Environment Committee (s) will also be notified to help protect against the site being subject to further alterations.  Prior to construction, operation and closure of the Project. The Environment Committee (s) will a source of the Project. The Environment Lorentitee (s) will be accepted and construction, operation and closure of the Project. Pacilitate the use of Traditional knowledge in Project-cated acti									
This could occur due to ground disturbances during site preparation activities within the Project  Development Area.  If chance finds or deeply buried archaeolagical resources in Organic deposits beneath lakes, marshes and peal) are encountered during the construction phase, a Chance Find Procedure (Appendix 5-6) will be implemented and the site will be secured.  The MCM will be notified and all activities impacting the affected archaeological resources (including paleontological resources) will case immediately. A licensed archaeologist will carry out an archaeological assessment following the Construction Procedure (Appendix 5-6) will be implemented and the site will be secured.  The MCM will be notified and all activities impacting the affected archaeological resources will cease immediately. A licensed archaeologist swill carry out an archaeological assessment following the Constunct Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Countee(s) will be a participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will a mit to a Project Totalitical knowledge in Project-related activities during construction, operation and closure of the Project.  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project.  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project.  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project.	resources from original context during construction,				1 -	on archaeology are not anticipated.			
This could occur due to ground disturbances during step perparation activities within the Project  Development Area.    A	operation and closure.	•	_	_					
and documented historical use and occupation of the PDA and LSA.    Formation   Formation									
Development Area.  If chance finds or deeply buried archaeological resources (including paleontological resources in organic deposits beneath lakes, marshes and peat) are encountered during the construction phase, a Chance Find Procedure (Appendix S-6) will be implemented and the site will be secured. The MCM will be notified and all sufficient participated archaeologist will carry out an archaeological resources will cease immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  * Facilitate communications and meaningful engagement during construction, operation and closure of the Project, and,  * Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					and operation. Staff training will also include a brief history of the potential				
paleontological resources in organic deposits beneath lakes, marshes and peat) are encountered during the construction phase, a Chance Find Procedure (Appendix 5-6) will be implemented and the site will be secured.  The MCM will be notified and all activities impacting the affected archaeological resources will case immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project.  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project.  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					and documented historical use and occupation of the PDA and LSA.				
peat) are encountered during the construction phase, a Chance Find Procedure (Appendix S-6) will be implemented and the site will be secured. The MCM will be notified and all activities impacting the affected archaeological resources will cease immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with anehological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will ali mot  * * Facilitate the use of Tradition knowledge in Project, related activities during construction, operation and closure of the Project; and,  * * Facilitate the use of Tradition knowledge in Project, related activities during construction, operation and closure of the Project; and,  * * Facilitate the use of Tradition knowledge in Project, related activities during construction, operation and closure of the Project; and,  * * * * Facilitate the use of Tradition knowledge in Project, related activities during construction, operation and closure of the Project; and,  * * * * * * * * * * * * * * * * * * *	Development Area.				If chance finds or deeply buried archaeological resources (including				
Procedure (Appendix 5-6) will be implemented and the site will be secured.  The MCM will be notified and all activities impacting the affected archaeological resources will cease immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Enrichment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; Facilitate the use of Tradional knowledge in Project-related activities during construction, operation and closure of the Project; Activities the use of Tradional knowledge in Project-related activities during construction, operation and closure of the Project; and, Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					paleontological resources in organic deposits beneath lakes, marshes and				
The MCM will be notified and all activities impacting the affected archaeological resources will case immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; and,  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					peat) are encountered during the construction phase, a Chance Find				
archaeological resources will cease immediately. A licensed archaeologist will carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project, and, Share and evaluate land use information on archaeological resources, review Project approvals and environmental	•				Procedure (Appendix S-6) will be implemented and the site will be secured.				
carry out an archaeological assessment following the Ontario Heritage Act and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and, Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental		•	•	•	The MCM will be notified and all activities impacting the affected				
and the Standards and Guidelines for Consultant Archaeologists (MCM 2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					archaeological resources will cease immediately. A licensed archaeologist will				
2011).  If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  • Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  • Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  • Share and evaluate land use information on archaeological resources, review Project approvals and environmental					carry out an archaeological assessment following the Ontario Heritage Act				
If human remains are encountered, all activities will cease immediately and the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  • Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  • Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  • Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					and the Standards and Guidelines for Consultant Archaeologists (MCM				
the local police and coroner will be contacted. In situations where human remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project;  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					2011).				
remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and, Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					If human remains are encountered, all activities will cease immediately and				
remains are associated with archaeological resources, the MCM will also be notified to help protect against the site being subject to further alterations.  Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project; Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and, Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					the local police and coroner will be contacted. In situations where human				
Prior to construction, an Environment Committee(s) will be established and opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  • Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  • Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  • Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental		•	•	•	remains are associated with archaeological resources, the MCM will also be				
opportunities to participate offered to members of proximate Indigenous communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  • Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  • Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  • Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					notified to help protect against the site being subject to further alterations.				
communities during the construction, operation and closure of the Project. The Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					Prior to construction, an Environment Committee(s) will be established and				
Environment Committee(s) will aim to:  Facilitate communications and meaningful engagement during construction, operation and closure of the Project;  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental					opportunities to participate offered to members of proximate Indigenous				
<ul> <li>Facilitate communications and meaningful engagement during construction, operation and closure of the Project;</li> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental</li> </ul>					communities during the construction, operation and closure of the Project. The				
construction, operation and closure of the Project;  Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,  Share and evaluate land use information on archaeological resources, review Project approvals and environmental					Environment Committee(s) will aim to:				
<ul> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental</li> </ul>					Facilitate communications and meaningful engagement during				
<ul> <li>Facilitate the use of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental</li> </ul>		_			construction, operation and closure of the Project;				
Share and evaluate land use information, including information on archaeological resources, review Project approvals and environmental		•	•	•	Facilitate the use of Traditional knowledge in Project-related activities				
archaeological resources, review Project approvals and environmental					during construction, operation and closure of the Project; and,				
archaeological resources, review Project approvals and environmental					,				
					1 , , ,				
required									

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-22: Built Heritage Resources and Cultural Heritage Landscapes - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	Ор	מ	Proposed Mitigation Measures	Description	Characterization <sup>2</sup>	Significance of Residual Adverse Effect	Prediction Confidence
Built Heritage Resources and Cultural Heritage Lan	dscap	es Val	lued (	Component (Section 6.23)	•	•		
Area of Federal Jurisdiction: Indigenous people								
Linkage from other VCs: Outdoor Recreation (Sec.)	tion 6.	18), Tra	aditio	nal Land and Resource Use (Section 6.21)				
• Linkage to other VCs: Archaeology (Section 6.22)								
Without mitigation, there may be changes in the				Potential heritage properties in the LSA will be noted on applicable Project	With the proposed design and	Not applicable	Not applicable	High
presence of buildings / landscape features over 40				maps to identify the heritage status of the property to Project personnel.	mitigation measures, residual effects			
years old during construction, operation and					due to changes in BHRs and CHLs are			
closure.	•	_	-		not predicted and therefore a			
This could occur due to ground disturbances during					determination of significance is not			
site preparation activities within the Project					required.			
Development Area.								
Without mitigation, there may be alteration or				If potential heritage properties may be directly impacted, the property will	With the proposed design and	Not applicable	Not applicable	High
destruction of BHRs or CHLs during construction,				be evaluated in a CHER. If that report determines that the property has	mitigation measures, residual effects			
operation and closure.		_	_	cultural heritage value or interest, an HIA will be prepared to determine	due to the alteration or destruction of			
This could occur due to ground disturbances during				specific mitigation measures to be implemented, such as documentation,	BHRs and CHLs are not predicted and			
site preparation activities within the Project				salvaging or applying buffer zones, as appropriate.	therefore a determination of			
Development Area.					significance is not required.			

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





# Table 15-23: Human and Ecological Health - Summary of Potential Effects, Mitigation, Residual Effects and Significance

	Phase <sup>1</sup>		1		Residual Adverse Effect(s)				
Potential Effect(s)	Con	do	כו	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
	Surfac	e Wate	er Syst	ems (Sections 6.6, 6.7 and 6.8), Fish and Fish Habitat (Section 6.10), Vegetation Comm 5.17), Outdoor Recreation (Section 6.18), Traditional Land and Resource Use (Section 6		dlife and Wildlife Habitat (Section 6	.12)		
<ul> <li>Linkage to other VCs: Commercial Land and Rescond Without mitigation, there may be changes in human health during construction, operation and closure. This could occur due to site preparation activities that may affect air quality from the operation of Project equipment, and changes in water quality due to ground disturbances, seepage from the operation of the co-disposal facility and ore stockpiles and the discharge of treated effluent during operations.</li> </ul>	•	•	•	<ul> <li>Implement the mitigation measures for the potential effects on air quality (Section 6.2), including the following specific to dust:</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads;</li> <li>Vehicle speeds will be limited; and,</li> <li>A dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.</li> </ul>	With the proposed design and mitigation measures, residual effects on human health are not predicted and therefore a determination of significance is not required.	Not applicable	Not applicable	High	
	•	•	•	<ul> <li>Implement the mitigation measures for the potential effects on surface water (Section 6.6, 6.7, 6.8 and 6.9), including the following specific to water quality:</li> <li>An integrated water management system will be designed to collect and control all contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant) and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements;</li> <li>An erosion and sediment control plan will be implemented to manage runoff water around disturbed areas. The erosion and sediment control plan will be prepared prior to the construction phase with the purpose of minimizing site erosion and protecting surface water from sedimentation. The erosion and sediment control plan will provide further details on measures to minimize slope length and grade, ditching and diversion berms, contact water management ponds, use of natural vegetation buffers and runoff controls;</li> <li>Water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system. Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures;</li> <li>During operations and active closure, effluent will be discharged at a location where sufficient flow exists to reduce the potential for erosion and promote assimilation at the discharge location. A diffuser or other means could be used to encourage greater mixing and attenuation of the effluent plume at the discharge location, if required. Consistent with MECP Policy B-1-5, the mixing zone size will be minimized to the extent practical; and,</li> </ul>					





# Table 15-23: Human and Ecological Health - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				During operations and active closure, the effluent treatment plant will be designed and operated to produce an effluent quality appropriate for discharge to the environment in accordance with applicable regulatory requirements, including the MDMER. Best available technologies that are economical achievable (BATEA) will be considered for the effluent treatment plant to meet protection requirements. The effluent treatment plant will be refined with ongoing Project planning and engineering design, and as discharge criteria are finalized during the approvals process.				
Without mitigation, there may be changes in ecological health during construction, operation and closure.  This could occur due to site preparation activities that may affect air quality from the operation of Project equipment, and changes in water quality due to ground disturbances, seepage from the operation of the co-disposal facility and ore stockpiles and the discharge of treated effluent during operations.	•	•	•	<ul> <li>Implement the mitigation measures for the potential effects on air quality (Section 6.2.4), including the following specific to dust:</li> <li>Dust emissions from roads and mineral stockpiles will be controlled through the application of water spray and supplemented by dust suppressants if required;</li> <li>Site roads will be maintained in good condition, with regular inspections and timely maintenance completed to minimize the silt loading on the roads;</li> <li>Vehicle speeds will be limited; and,</li> <li>A dust management plan will be implemented to identify potential sources of fugitive dusts, outline mitigation measures that will be employed to control dust generation and detail the inspection and record keeping required to demonstrate that fugitive dusts are being effectively managed.</li> </ul>	With the proposed design and mitigation measures, residual effects on ecological health are not predicted and therefore a determination of significance is not required.	Not applicable	Not applicable	High
	•	•	•	<ul> <li>Implement the mitigation measures for the potential effects on surface water (Section 6.6.4, 6.7, 6.8.4 and 6.9.4), including the following specific to water quality:</li> <li>An integrated water management system will be designed to collect and control all contact water from the stockpiles, co-disposal facility and plant site areas. Collected contact water that is not recycled in ore processing will be treated at the effluent treatment plant) and discharged to the southeast arm of Springpole Lake in accordance with permitting requirements;</li> <li>An erosion and sediment control plan will be implemented to manage runoff water around disturbed areas. The erosion and sediment control plan will be prepared prior to the construction phase with the purpose of minimizing site erosion and protecting surface water from sedimentation. The erosion and sediment control plan will provide further details on measures to minimize slope length and grade, ditching and diversion berms, contact water management ponds, use of natural vegetation buffers and runoff controls;</li> <li>Water collection ditches will be constructed and operated around the perimeter of infrastructure, including the co-disposal facility and stockpiles to collect overland flow and seepage and direct it to the integrated water management system. Non-contact water will be diverted away from Project components using ditches, diversion berms and other suitable measures;</li> <li>During operations and active closure, effluent will be discharged at a location where sufficient flow exists to reduce the potential for erosion and promote assimilation at the discharge location. A diffuser or other means could be used to encourage greater mixing and attenuation of the effluent plume at</li> </ul>				





## Table 15-23: Human and Ecological Health - Summary of Potential Effects, Mitigation, Residual Effects and Significance

		Phase	e <sup>1</sup>			Residual Adverse Effect(s)		
Potential Effect(s)	Co Co		ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				the discharge location, if required. Consistent with MECP Policy B-1-5, the				
				mixing zone size will be minimized to the extent practical; and,				
				During operations and active closure, the effluent treatment plant will be				
				designed and operated to produce an effluent quality appropriate for				
				discharge to the environment in accordance with applicable regulatory				
				requirements, including the MDMER. Best available technologies that are				
				economical achievable (BATEA) will be considered for the effluent treatment				
				plant to meet protection requirements. The effluent treatment plant will be				
				refined with ongoing Project planning and engineering design, and as				
				discharge criteria are finalized during the approvals process.				

- 1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase
- 2 Bolded text indicates a key mitigation measure.
- 3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect, and Level III is indicative of a high potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.





		Phase	1			Residual Adverse Effect(s)			
Potential Effect(s)	Con	do	C	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence	
	source			on 6.17), Outdoor Recreation (Section 6.18), Local and Regional Economy (Section 6.19) leritage Landscapes (Section 6.23), Human and Ecological Health (Section 6.24)	), Local and Regional Infrastructure and Se	ervices (Section 6.20), Traditional Lar	nd and Resource Use	e (Section 6.21),	
Without mitigation, there may be changes in Indigenous health conditions during construction, operation and closure.  This could occur due to site preparation activities that may affect air quality and sound levels from equipment, ground disturbance that may affect water quality and subsequently country foods.	•	•	_	Development of a compact mine site to limit the areal extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake.  Maintain Project designs such that no new public access points are developed on	With the implementation of mitigation measures, there is no residual effect due to changes in Indigenous health conditions during any phase of the	Not applicable	Not applicable	Moderate	
	•	-	-	Springpole Lake.  Building dimensions, layout and orientation will be designed to shield noise	Project.				
	•	•	•	During construction, operation and closure phases of the Project, implement the mitigation measures relevant to Indigenous health conditions for air quality (Section 6.2.4), noise and vibration (Section 6.3.4), surface water (Section 6.6.4, Section 6.7.4 and Section 6.8.4), fish and fish habitat (Section 6.10.4), vegetation communities and wetlands (Section 6.11.4), and wildlife and wildlife habitat (Section 6.12.4).					
	•	•	_	Maintain regular communication with trapline holders SL197 and SL 200 regarding activities and opportunities to facilitate their land use activities.					
	•	•	•	-	Prior to construction, establish an alternate portage route identified to maintain access between Springpole Lake and Birch Lake, and maintain the alternate route until post closure when the existing portage has been re-established.				
	•	_	•	Undertake revegetation in the mine site area, where practical, and include input from Indigenous communities and traditional land and resource use information planning documents.					
	•	•	•	During construction, operation and closure phases of the Project, support community land-based cultural activities.					
Without mitigation, there may be changes in Indigenous socio-economic during construction, operation and closure.	•	•	_	Development of a compact mine site to limit the areal extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake.	Given the total area available for trapping, the change in area due to the Project footprint is small, and	Ecological and Social Context: Level   Magnitude: Level	Not Significant	Moderate	
This could occur due to changes in navigation and other recreational uses, commercial activities, food security, income inequity and other changes to community level socio-economic conditions from Project activities, including employment and Project expenditures.	•	•	•	During construction, operation and closure phases of the Project, implement the mitigation measures relevant for Indigenous socioeconomic conditions for air quality (Section 6.2.4), noise and vibration (Section 6.3.4), surface water (Section 6.6.4, Section 6.7.4 and Section 6.8.4), vegetation communities and wetlands (Section 6.11.4), and wildlife and wildlife habitat (Section 6.12.4).	through information sharing using the Environment Committee, and the development of an access management strategy, the effects will be minimized.	Geographic Extent: Level   Duration: Level     Frequency:   Reversibility: Level			
	•	•	•	Give preference to hiring employees for the Project to Indigenous communities and local municipalities.	With the implementation of mitigation measures, the residual effect is a				
	•	•	•	Give preference to contracting for goods and services from the businesses in the Indigenous communities and local municipalities.	localized change in trapping with the local study area during all phases of				
	•	•	•	Establish a Health and Wellness Strategy (Appendix Q-3) focused on employee mental health and wellness to complement health and safety programs and to support local and Indigenous employees.	the Project, which occurs once and will be partially reversed at closure.				





		Phase <sup>1</sup>	ı			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	CI	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	•	-	Provide onsite accommodations that are safe and welcoming for the Project workforce during construction and operations phases.				
	•	•	_	The construction and operation of the Project will utilize a rotational workforce to support the employment of local and regional workers.				
	•	•	•	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities, during construction, operation and closure phases.				
Without mitigation, there may be changes in Indigenous physical and cultural Heritage during construction, operation and closure.  This could occur due to site preparation activities for the construction of mine site infrastructure, the mine access road and the transmission line, ongoing maintenance of the infrastructure, and the activities associated with final reclamation at closure.	•	•	I	Development of a compact mine site to limit the areal extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake.	Given the total area available for trapping, the change in area due to the Project footprint is small, and	Ecological and Social Context: Level   Magnitude: Level	Not Significant	Moderate
	•	•	-	Maintain Project designs such that no new public access points are developed on Springpole Lake.	through information sharing using the Environment Committee, and the	Geographic Extent: Level I  Duration: Level III		
	•	•	-	Preserve a tree line as a buffer around the mine site to diminish the amount of the mine site that can be seen. This buffer around the Project will be maintained wide enough to withstand the loss of trees, such as those toppled by wind.	development of an access management strategy, the effects will be minimized. With the implementation of mitigation	Frequency:     Reversibility: Level		
	•	_	_	Building dimensions, layout and orientation will be designed to shield noise sources, where possible.	measures, the residual effect on the changes in the value of physical and			
	•	•	•	During construction, operation and closure phases of the Project, implement the mitigation measures for archaeology (Section 6.22.4) and cultural heritage (Section 6.23.4).	cultural heritage resource is low. The residual effect will be confined to the Project Development Area, occur			
	•	-	-	Prior to construction, provide opportunities to Indigenous communities that reported traditional land and resource use in the local study area to elaborate on site-specific information with the goal to refine mitigation measures, if required.	continuously until closure, and will be partially reversible with revegetation.			
	•	•	•	During construction, operation and closure phases of the Project, support community land-based cultural activities.				
	_	_	•	All buildings and facilities will be deconstructed and removed, and disturbed areas will be stabilized during closure.				
Without mitigation, there may be changes in the current use of lands and resources for traditional purposes during construction, operation and	•	•	I	Development of a compact mine site to limit the areal extent of disturbance including a mine footprint of 867 ha including minimizing the open pit mining area to 6% of Springpole Lake.	Effects to traditional harvesting activities will be restricted to the immediate area around the Project	Ecological and Social Context: Level   Magnitude: Level	Not Significant	Moderate
closure. This could occur due to site preparation activities for	•	•	-	Maintain Project designs such that no new public access points are developed on Springpole Lake.	footprint and minimized with the development of an access	Geographic Extent: Level I Frequency: I		
the construction of mine site infrastructure, the mine access road and the transmission line, ongoing	•	•	_	Preserve a tree buffer around the mine site to diminish the amount of the mine site that can be seen.	management strategy and the development of alternate navigation	Duration: Level III Reversibility: Level II		
maintenance of the infrastructure, and the activities associated with final reclamation at closure.	•	_	_	Building dimensions, layout and orientation will be designed to shield noise sources, where possible.	route. With the implementation of mitigation			
	•	•	•	During construction, operation and closure phases of the Project, implement the mitigation measures relevant to current use for air quality (Section 6.2.4), noise and vibration (Section 6.3.4), surface water (Section 6.6.4, Section 6.7.4 and Section 6.8.4)), fish and fish habitat (Section 6.10.4), vegetation communities and wetlands (Section 6.11.4), and wildlife and wildlife habitat (Section 6.12.4).	measures, there will be a residual effect on the current use of lands and resources for traditional purposes due to a in abundance of harvested species, changes in access and experience. The residual effect will be			





		Phase	1			Residual Adverse Effect(s)		
Potential Effect(s)	Con	do	ס	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
	•	-	-	Where there is interest, provide opportunities to local Indigenous communities and traditional land users to harvest plants and aquatic resources within the Project Development Area prior to construction.	confined to the local study area, occur once but continue until closure when it will be partially reversible.			
	•	•	•	During construction, operation and closure phases of the Project, support community land-based cultural activities.				
	•	_	_	Support the development and delivery of Indigenous led ceremonies on site to pay respect to the land, air and water prior to construction and at other key Project milestones.				
	•	•	•	Facilitate the development and implementation of a community-based monitoring program to supplement (not duplicate) regulatory monitoring requirements.				
	•	•	•	During construction, operation and closure phases, engage Indigenous environmental monitors from local communities in the implementation of mitigation and monitoring measures.				
	•	•	•	Hunting and fishing at the Project will be prohibited by employees and contractors while at site, during all phases.				
	•	•	•	<ul> <li>Prior to construction, provide the opportunity to establish Environment</li> <li>Committee(s) with interested Indigenous communities to:         <ul> <li>Facilitate on-going communications and meaningful engagement during construction, operation and closure of the Project;</li> <li>Facilitate the sharing and integration of Traditional knowledge in Project-related activities during construction, operation and closure of the Project; and,</li> <li>Share and evaluate environmental information, review Project approvals and environmental management and monitoring plans, participate in adaptive management and identify mitigation measures, address emerging issues and areas of interest identified by communities.</li> </ul> </li> </ul>				
	•	_	_	Local Indigenous communities and identified points of reception will be advised ahead of transmission line construction work periods and as the construction work proceeds.				
	•	_	-	Work with local Indigenous communities to coordinate construction activities related to the transmission line to minimize overlap with the timing of traditional land use activities (e.g., fall moose hunt) and other sensitive periods.				
	•	•	-	Support reasonable requests and work schedule flexibility for Indigenous employees for time off to pursue traditional land use activities, during construction, operation and closure phases.				
	•	-	-	Prior to construction, develop an access management strategy Plan with local Indigenous communities to manage access in the along the mine access road, north of the Birch River crossing, during construction, operation and closure phases of the Project, with the purpose of supporting TLRU access and minimizing new public access.				
	•	•	-	Prior to construction, establish an alternate portage route identified to maintain access between Springpole Lake and Birch Lake, and maintain the				





	Phase <sup>1</sup>				Residual Adverse Effect(s)			
Potential Effect(s)		do	ū	Proposed Mitigation Measures <sup>2</sup>	Description	Characterization <sup>3</sup>	Significance of Residual Adverse Effect	Prediction Confidence
				alternate route until post closure when the existing portage has been re-				
				established.				
	_			All buildings and facilities will be deconstructed and removed, and disturbed areas				
				will be stabilized during closure.				
				During the operation and closure of the Project, undertake revegetation in the				
	_	•	•	mine site area, where practical, and include input from Indigenous communities				
				and traditional land and resource use planning documents.				

#### Notes:

1 Con = Construction phase; Op = Operations phase; and, Cl = Closure phase

2 Bolded text indicates a key mitigation measure.

3 Level I is indicative of a negligible or low potential to contribute to an overall significant environmental effect. Level II represents an intermediate condition.